

PREVENTIV PARAPRAK

Objekti: "Rikonstrukcion i rruges Rragam - Sheldi Loti 1"

Nr.	Analiza	Emertimi i Punimeve	Njësia	Sasia	Cmimi	Vlera
1	Punime Germimi dhe Mbushje ne Rruge					
1	3.104/a	Germim dheu me ekskavator zingjir 0.5 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria IV, me shk ne mjet	m ³	560.00		-
2	3.98/a	Germim dheu me ekskavator goma 0.25m ³ , per kanalin anesore, toke e zakonshme, kategoria III, shkarkim ne mjet	m ³	1,290.00		-
3	3.48/b	Rrafshim skarpate me krahe ne germim e mbushje, toke e zakonshme	m ²	1,350.00		-
4	3.184/a	Shtrese zhavorr lumi t=30cm, me cilindrim (per kasoneten)	m ²	460.00		-
5	3.158/5a	Transport dheu me auto deri ne 5km	m ³	1,850.00		-
6	An.164/1 b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	385.00		-
		Shuma 1	1			-
2	Punime shtresash rrugore					
1	3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m ²	3,780.00		-
2	3.228/1	Shtrese binderi me zall lavatrice, 4cm, me makineri	m ²	3,780.00		-
3	3.212/b	Shtrese stabilizant t=10cm	m ²	5,670.00		-
4	3.212/b	Shtrese stabilizanti, t=1x10 cm, (bankinë)	m ²	1,270.00		-
5	3.212	Shtrese çakelli t=10/15cm, makadam, perhapur e ngjeshur makineri	m ²	3,906.00		-
6	3.198	Cilindrim kasonete me rrul	m ²	5,670.00		-
		Shuma 2	2			-
3	Punime te ndryshme					
1	An-49	Prishje struktura ekzistuese betoni	m ³	7.30		-
2	2.426/2	Prishje mure blloqesh betoni (mure rrethues)	m ³	10.00		-
3	3.268	FV tombino kendrejte b/a C 16/20	m ³	5.60		-
4	3.244/1	Struktura te holla monolite betoni C 20/25	m ³	13.60		-
5	An1	Guardrail- N2 anesore me 2 valez. ne 1 ane, W2 + aksesori	ml	23.00		-
		Shuma 3	3			-
4	Punime ne sinjalistiken rrugore					
1	An47	Tabele katrore e vogel me A=40 (shevrone)	copë	2.00		-
2	An94	Tabela katrore normale me diagonale vertikave 60x40	copë	1.00		-
3	An100	Tabele rrethi "detyrim" normal me D = 60	copë	6.00		-
4	An106	Tabela trekendore normal me A = 90	copë	4.00		-
5	An151	Vizime me boje bikomponente	m ²	270.00		-
6	An145	Boje termoplastike (sprajt)	m ²	10.00		-
6	An160	FV tabela te medha informative + bazamenti "L" 5.5x3m	copë	1.00		-
		Shuma 4	4			-
		Shuma				-
		Fond Rezerve	2%			-
		Shuma me Fond Rezerve				-
		TVSH 20 %	20%			-
		Shuma Totale me TVSH				-

Preventivues
Shoqëria "LENI - ING" sh.p.k

Ing.Nikoll PALUCA

Ing.Maltin GRABOVAJ