

PREVENTIV

OBJEKTI : "SISTEMIM ASFALTIM I PJESEVE TE DEMTUARA TE ASFALTIT NE RRUGET E BASHKISE"

Nr.	Nr.Man	Pershkrimi I Punimeve	Njesia	Sasia	Cmimi	Vlera
	1	Rruga Dorez (kthesa Qarrishtes-Kraste)				
1	An	Prerie Asfalti me makineri	ml	520		
2	3.87/b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke(germim per heqje te materialit te demtuar dhe nderhyrja ne nenshtresa)	m ³	55		
3	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	55		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	260		
5	3.212/b	Shtrese stabilizant t=10cm	m ²	260		
6	3.222/2	Shtrese Bineri me granil gur kavo 6 cm me makineri	m ²	260		
7	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	260		
8	3.334	Gabion me rriete teli te zinguar gur kave 1x2x2 m	m ³	150		
		Shuma 1				
	2	Rruga Kuterman (kthesa Kuturman -qender fshati)				
1	An	Skarifikim shtrese Asfalti me makineri	m ²	486		
	An	Sperkatje me emulsion bituminoz 0.5 l/m ²	m ²	486		
2	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	486		
		Shuma 2				
	3	Rruga Polis (ura fshatit - godina njesise administrative)				
3	An	Prerie Asfalti me makineri,	ml	700		
1	3.222/2	Shtrese Bineri me granil gur kavo 6 cm me makineri	m ²	360		
2	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	360		
		Shuma 3				
	4	Rruga Xhyre (kthesa Xhyres -shkolla)				
1	An	Prerie Asfalti me makineri	ml	200		
2	3.87/b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke(heqjn e materialit te demtuar dhe nderhyrja ne nenshtresa)	m ³	22		
3	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	22		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	88		
5	3.212/b	Shtrese stabilizant t=10cm	m ²	88		
6	3.222/2	Shtrese Bineri me granil gur kavo 6 cm me makineri	m ²	88		
7	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	88		
		Shuma 4				

	5	Rruga Dardhe (kthesa per Dardhe - qender fshati)				
1	An	Prerie Asfalti me makineri	ml	500		
2	3.87/b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke (heqjn e materialit te demtuar dhe nderhyrja ne nenshtresa)	m ³	45		
3	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	45		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	220		
5	3.212/b	Shtrese stabilizant t=10cm	m ²	220		
6	3.222/2	Shtrese Bineri me granil gur kavo 6 cm me makineri	m ²	220		
7	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	220		
		Shuma 5				
	6	Rruga Hotolisht (rruga nacionale - fundi i fshatit HotolishtQender)				
1	An	Skarifikim shtrese Asfalti me makineri	m ²	1,944		
2	An	Sperkatje me emulsion bituminoz 0.5 l/m ²	m ²	1,944		
3	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	1,944		
		Shuma 6				
	7	Rruga Iliria, prane ish-orendreqesit, Qyteti Librazhd				
1	An	Skarifikim shtrese Asfalti me makineri	m ²	750		
2	An	Sperkatje me emulsio bituminoz 0.5 l/m ²	m ²	750		
3	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	750		
		Shuma 7				
	8	Rruga Qazim Murtini (rruga e Spitalit) Qyteti Librazhd				
1	An	Skarifikim shtrese Asfalti me makineri	m ²	3,200		
2	2.426/3	Prishje shtresa betoni , kunete ekzistuese	m ³	24		
3	2.262/3	Shtrese betoni C 12/15 per kunete	m ³	24		
7	An	Sperkatje me emulsio bituminoz 0.5 l/m ²	m ²	3,200		
8	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	3,200		
		Shuma 8				
	9	Rruga 10-Nentori, (rruga varrezave te deshmoreve) Qyteti Librazhd				
1	An	Skarifikim shtrese Asfalti me makineri	m ²	2,200		
2	2.426/3	Prishje shtresa betoni	m ³	9		
3	3.87/b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke, ndertim traseje ne hyrje te rruges Poda	m ³	30		
4	3.616	F V bordura betoni 12x25cm,(nga cepi ures deri tek hyrja e rruges Poda)	ml	26		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	90		
5	3.212/b	Shtrese stabilizant t=10cm	m ²	90		
5	3.222/2	Shtrese binderi me granil gur kavo 6 cm me makineri	m ²	60		
6	2.262/3	Shtrese betoni C 12/15 per kunete	m ³	12		
7	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	2,260		

		Shuma 9				
	10	Rruga Libaro (tek axhensia qytetit)Librazhd				
1	An	Skarifikim shtrese Asfalti me makineri	m ²	844		
3	An	Sperkatje me emulsio bituminoz 0.5 l/m2	m ²	844		
4	2.262/3	Shtrese betoni C 12/15 per kunete	m ³	6.80		
5	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	844		
		Shuma 10				
	11	Sheshi tek ish-Garazhet e Komunales, pallatet e Shejes,qyteti Librazhd				
1	3.87/b	Germim dheu me ekskavator goma, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke(heqjn e materialit te demtuar dhe nderhyrja ne nenshtresa)	m ³	144		
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	144		
4	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	806		
4	3.212/b	Shtrese stabilizant t=10cm	m ²	999		
5	3.222/2	Shtrese Bineri me granil gur kavo 6 cm me makineri	m ²	806		
6	3.226/1	Shtrese Asfaltobeton me granil gur kavo 4 cm me makineri	m ²	806		
7	3.620	Shtrim sheshi dhe trotuar me 6 cm beton, me pllaka betoni	m ²	193		
8	3.616	F V bordura betoni 12x25cm	ml	64		
9	An - 7	F.V Tuba PVC Ø 315 mm per linja te jashtme	ml	60		
10	An - 18	Pusete shkarkimi 50 x 50, h = 80 cm,kapak betoni	cope	4		
		Shuma 11				
		SHUMA(1 deri ne11)				
		Tvsh 20%				
		TOTALI				