

Nr.anal	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
	I - PUNIME PRISHJE				
An2.197	Prishje hidroizolim tarace (Banjot)	m2	562		
An.2.239a	Prishje termoizolim tarace	m3	56.2		
2.426/3	Prishje shtrese betoni tarace	m3	56.2		
2.426/4	Prishje soleta b/a	m3	17.2		
2.426/7	Prishje kollona, trare b/a	m3	7.6		
2.426/3	Prishje shtrese betoni veranda	m3	12.2		
2.426	Prishje mur tulle pa pastrim	m3	53.5		
2.426/7	Prishje arkitrare b/a dritare e dyer	m3	9.1		
An2,295	Prishje tavani kallama + suva	m2	454		
An2,303	Prishje suvatim tavani	m2	908		
An2.310	Prishje suvatim muri brenda	m2	3432		
An2,370	Cmontim dritare druri	m2	91		
An2.395	Cmontim dritare duralumini	m2	91		
An2,388	Cmontim dyer druri	m2	91.6		
An2,390/1	Cmontim dere metalike	m2	10.4		
An2,405	Prishje davancale garnili te derdhur dritare	m2	51		
An2,268	Prishje shtrese granili shkalle	m2	67		
An2.266	Prishje shtrese pllaka cimentoje	m2	1450		
An2.504	Cmontim WC allaturka	cope	24		
An2,495	Cmontim lavamane porcelani	cope	6		
Analize	Cmontim instalime hidraulike	leke	1		
2.37/5a	Transport mbeturina ndertimi me auto deri ne 5 km	m3	400		
	SHUMA - I	leke			
	II - OBJEKTI EGZISTUES				
	I - Punime germimi				
2.5	Germim e mbushje dheu me krah kategoria III per themele, h = 1.5m	m3	5.2		
	Shuma - 1	leke			
	2 - Punime murature				
2.70/2	Mur me tulle te lehtesuara dopio deri 3m me llaç perzier M25	m3	35.2		
	Shuma - 2	leke			
	3 - Punime betoni e b/a				
2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20	m3	3.62		
2.118/1	Kollona b/a monolite C - 16/20, h ~ 8 m	m3	3.4		
2.119/1a	Trare e arkitrare b/a C20/25 h ~ 4m	m3	1.9		
2.119/1	Arkitrare b/a C - 16/20, h ~ 4 m	m3	8.1		
	Shuma - 3	leke			
	4 - Punime hekur betoni e konstruksioni				
2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.8		
2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.4		

2.181	Konstruksione metalike te perbera streha e verandes + shkallet e emergjences + lyerje	ton	11.2		
	Shuma - 4	leke			
	5 - Punime hidroizolimi e catie				
2.239/a	Shtrese termoizoluese me polisterol t=10 cm	m3	56		
2.262/4	Shtrese betoni C 16/20 mbi polisterol	m3	56		
2.166	F V hekur betoni periodik Ø 6 mm zgare ne shtrese	ton	0.6		
2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m2	580		
2.203	Veshje korrnize llamarine xingat	m2	78		
2.206	Kasete shkarkimi me llamarine xingat	cope	2		
2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	24		
2.195	Hidroizolim me emulsion dhe dy duar bitumbanjo	m2	66		
2.256/b	Mbulim çatie me panele sanduich streha verandes	m2	80		
2.521	Tub kanalizimi pvc Ø 140 mm mbledhja e ujrave te shiut	ml	50		
	Shuma - 5	leke			
	6 - Punime shtresash				
2.258	Nenshtrese zhavori veranda + shkalla emergjences +banjo katit per dhe	m3	14.3		
2.262/4	Shtrese betoni C 16/20 shkallet e jashtme	m3	31.4		
2.262/4	Shtrese betoni C 16/20 nivelimi dyshemeve t=6cm	m3	90.9		
2.267/a	Shtrese me pllaka grez porcelanato	m2	1470		
2.268/a	Shkalle montazhi mermeri	m2	67		
2.268/a	Pragje montazhi mermeri	m2	47.3		
2.291	Bordura trotuari 25x12cm te derdhura ne vend	ml	130		
3.620	Trotuar, me 6 cm beton, me pllaka	m2	110		
	Shuma - 6	leke			
	7 - Punime tavani e suvatimi e veshje				
2.297/b	Tavan i varur me pllaka gipsi 60x60cm	m2	450		
2.300/1	Suva solete h ~ 4 m me drejtues, me pompe	m2	1931		
2.297/a	Tavan me kartonxhes streha verandes	m2	90.6		
2.310/1	Suva brenda mur tulle h~4m me pompe, llaç perzier M 25	m2	4144		
2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suva.	m2	1028		
2.308/a	Suvatim me grafiato h > 4 m	m2	1028		
2.326	Veshje me pllake majolike	m2	341		
2.324/b	Plintuse grez importi, h = 10 cm	ml	847		

2.279	Derrasa FM 2.5cm b=10cm ne kuote 80cm nga dysHEMEJA ne mure	m2	84		
	Shuma - 7	leke			
	8 - Punime dyer dritare				
2.375/a	Dritare d/alumini dyfish xham.	m2	186.8		
2.395/a	Dyer d/alumini dopio xham. Dyert e jashtme	m2	22		
2.395/a	Dere d/alumini pa xham, me mbushje d/a. banjo	m2	23.8		
2.383/1	F V dyer te brendeshme druri importi cilesi e I-re.	m2	69.3		
	Shuma - 8	leke			
	9 - Punime bojatisje e lyerje				
2.404	Boje hidroplastike brenda	m2	6553		
2.400	Boje vaji siperfaqe druri	m2	210		
	Shuma - 9	leke			
	10 - Punime te ndryshme				
2.409	Parapet shkalle e ballkone mur tulle+suva+koriman druri	m2	24.4		
2.413	F.V zgara dekorativa hekuri me figuracion mesatare dritare	ton	1.3		
3.837/a	Rrethim me rrjete teli shkallet e emergjences	m2	164		
	Shuma - 9	leke			
	SHUMA - II				
	III - GODINA KALDAJES				
	I - Punime germimi				
2.5	Germim e mbushje dheu me krah kategori III per themele, h = 1.5m	m3	7		
2.375/a	Transport mbeturina ndertimi me auto deri ne 5 km	m3	8		
	Shuma - 1	leke			
	2 - Punime murature				
2.70/2	Mur me tulle te lehtesuara dopio deri 3m me llaç perzier M25	m3	14.5		
2.860	Mur me tulle me 6 vrime, t=12cm, h~3m, llaç perzier M15	m3	2		
	Shuma - 2	leke			
	3 - Punime betoni e b/a				
2.114/1	Plinta e bazamente betoni monolite deri 20 m3 C - 16/20	m3	5.4		
2.118/1	Kollona b/a monolite C - 16/20, h ~ 8 m	m3	0.7		
2.121/1	Brez b/a C 16/20, h ~ 8 m	m3	2.6		
2.158	Soleta te plota b/a C 16/20	m3	5.3		
2.119/1	Arkitrare b/a C - 16/20, h ~ 4 m	m3	0.08		
	Shuma - 3	leke			

	4 - Punime hekur betoni e konstruksioni				
2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.55		
2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.35		
	Shuma - 4	leke			
	5 - Punime hidroizolimi e catie				
2.262/4	Shtrese betoni C 16/20	m3	2.35		
2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m2	45		
2.203	Veshje korrnize llamarine xingat	m2	7		
2.206	Kasete shkarkimi me llamarine xingat	cope	1		
2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	3		
	Shuma - 5	leke			
	6 - Punime shtresash				
2.258	Nenshtrese zhavori	m3	3		
2.262/4	Shtrese betoni C 16/20 dysHEME	m3	3		
2.262/4	Shtrese betoni C 16/20 nivelimi dysHEMEVE t=6cm	m3	1.8		
2.266	Shtrese me pllaka granili te zakonshme 30x30 cm	m2	30		
2.268/a	Shkalle montazhi mermeri	m2	0.3		
	Shuma - 6	leke			
	7 - Punime tavani e suvatimi e veshje				
2.300/1	Suva solete h ~ 4 m me drejtues, me pompe	m2	28		
2.310/1	Suva brenda mur tulle h~4m me pompe, llac perzier M 25	m2	83		
2.331	Suva e zakonshme fasade mur tulle h ~ 8 m	m2	90		
2.324a	Plintuse pllake grez	ml	847		
	Shuma - 7	leke			
	8 - Punime dyer dritare				
2.390/1	F.V dyer metalike me llamarine te zeze 27.75 kg/m2 perfshi lyerjen	m2	2.1		
	Shuma - 8	leke			
	9 - Punime bojatisje e lyerje				
2.404	Boje hidroplastike brenda	m2	177		
	Shuma - 9	leke			
	SHUMA - III				
	IV - GODINA E RE				
	1 - Punime germimi				
2.3	Germim themele e plinta b>2m, ekskavator me goma, kova 0.25m3 shkarkim auto (zbankim)	m3	120		
2.26/a	Germim themele e plinta b~2m, ekskavator me goma, kova 0.25m3 shkarkim auto	m3	469		
2.5	Germim e mbushje dheu me krah kategoria III per	m3	31		

	<i>themele, h = 1.5m</i>				
2.3	<i>Nenshtrese zhavori mbushja e themeleve</i>	<i>m3</i>	<i>50</i>		
2.37/5a	<i>Transport mbeturina ndertimi me auto deri ne 5 km</i>	<i>m3</i>	<i>650</i>		
	Shuma - 1	leke			
	2 - Punime murature				
2.70/2	<i>Mur me tulle te lehtesuara dopio deri 3m me llaç perzier M25</i>	<i>m3</i>	<i>317</i>		
2.70/2	<i>Mur me tulle te lehtesuara 20 cm deri 3m me llaç perzier M25 ndares e parapete</i>	<i>m3</i>	<i>36.6</i>		
2.860	<i>Mur me tulle me 6 vrima, t=12cm, h~3m, llaç perzier M15</i>	<i>m3</i>	<i>3</i>		
	Shuma - 2	leke			
	3 - Punime betoni e b/a				
2.262/4a	<i>Pllake themeli, trare e bazamente b/a C 20/25</i>	<i>m3</i>	<i>241</i>		
An2.111/2	<i>Mure betoni C - 12/15</i>	<i>m3</i>	<i>26</i>		
2.117/1b	<i>Kollona b/a monolite C 25/30 h ~ 4m</i>	<i>m3</i>	<i>76.3</i>		
An2.119/1a	<i>Trare e arkitrare b/a C25/30 h ~ 4m</i>	<i>m3</i>	<i>102.1</i>		
An2.122/1a	<i>Soleta te plota b/a C 20/25 t = 10 cm, h ~ 4m</i>	<i>m3</i>	<i>315.3</i>		
2.119/1	<i>Arkitrare b/a C - 16/20, h ~ 4 m</i>	<i>m3</i>	<i>5.8</i>		
2.117/1	<i>Kollona b/a monolite C - 16/20, h ~ 4 m kolonizat e parapetit soletes</i>	<i>m3</i>	<i>1.6</i>		
2.121/1	<i>Brez b/a C 16/20, h ~ 8 mm bi murin e parapetit</i>	<i>m3</i>	<i>4.3</i>		
	Shuma - 3	leke			
	4 - Punime hekur betoni e konstruksioni				
2.166	<i>F V hekur betoni periodik Ø 6 - 10 mm</i>	<i>ton</i>	<i>40</i>		
2.167	<i>F V hekur betoni periodik Ø > 10 mm</i>	<i>ton</i>	<i>67.6</i>		
2.413	<i>F.V zgara dekorativa hekuri me figuracion mesatare dritare</i>	<i>ton</i>	<i>1.3</i>		
2.181	<i>Konstruksione metalike te perbera mbulesa palestres + lyerje</i>	<i>ton</i>	<i>13</i>		
	Shuma - 4	leke			
	5 - Punime hidroizolimi e catie				
2.70/2	<i>Mur me tulle te lehtesuara 20 cm deri 3m me llaç perzier M25 parapete tarace</i>	<i>m3</i>	<i>22.6</i>		
2.239/a	<i>Shtrese termoizoluese me polisterol t=10 cm</i>	<i>m3</i>	<i>49.7</i>		
2.262/4	<i>Shtrese betoni C 16/20</i>	<i>m3</i>	<i>49.7</i>		
2.166	<i>F V hekur betoni periodik Ø 6 mm zgare ne shtrese</i>	<i>ton</i>	<i>1.25</i>		
2.197	<i>Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama</i>	<i>m2</i>	<i>568</i>		

2.203	Veshje korrnize llamarine xingat	m2	101.5		
2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	62		
2.206	Kasete shkarkimi me llamarine xingat	cope	5		
2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	46		
2.195	Hidroizolim me emulsion dhe dy duar bitumbanjo	m2	48		
2.256/b	Mbulim çatie me panele sanduich palestra	m2	558		
	Shuma - 5	leke			
	6 - Punime shtresash				
2.258	Nenshtrese zhavori veranda + shkalla emergjences +banjo katit perdhe	m3	105		
2.262/4	Shtrese betoni C 16/20 shkallet e jashtme	m3	105		
2.166	F V hekur betoni periodik Ø 6 mm zgare ne shtresen e dyshemese	ton	2.4		
2.262/4	Shtrese betoni C 16/20 nivelimi dyshemeve t=7cm	m3	89		
2.267/a	Shtrese me pllaka grez porcelanato	m2	1272		
2.279	Derrasa FM 2.5cm b=10cm dyshemeja palestres	m2	567		
2.268/a	Pragje montazhi mermeri	m2	38.4		
2.291	Bordura trotuari 25x12cm te derdhura ne vend	ml	87.5		
3.620	Trotuar, me 6 cm beton, me pllaka	m2	90		
	Shuma - 6	leke			
	7 - Punime tavani e suvatimi e veshje				
2.300/1	Suva solete h ~ 4 m me drejtues, me pompe	m2	1272		
2.310/1	Suva brenda mur tulle h~4m me pompe, llaç perzier M 25	m2	3990		
2.358/b	Veshje fasade me polisterol kompakt jeshil t=5cm + rrjete + suva.	m2	1476		
2.308/a	Suvatim me grafiato h > 4 m	m2	1475		
2.326	Veshje me pllake majolike	m2	145		
2.324/b	Plintuse grez importi, h = 10 cm	ml	1039		
2.279	Derrasa FM 2.5cm b=10cm ne kuote 80cm nga dyshemeja ne mure	m2	118		
An	Rrjete me litare Ø 4 mm ne brezin e poshtem te kapriatave me kuadrate 10x10cm	ml	5600		
	Shuma - 7	leke			
	8 - Punime dyer dritare				
2.375/a	Dritare d/alumini dyfish xham.	m2	205.4		
2.386/2	Dyer te blinduara importi.	m2	4.2		

2.395/a	Dere d/alumini pa xham, me mbushje d/a. banjo	m2	8.6		
2.383/1	F V dyer te brendeshme druri importi cilesi e I-re.	m2	40.8		
	Shuma - 8	leke			
	9 - Punime bojatisje e lysterje				
2.404	Boje hidroplastike brenda	m2	6806		
2.400	Boje vaji sipërfaqe druri	m2	295		
	Shuma - 9	leke			
	SHUMA - IV				
	V - PUNIME RRETHIMI E SISTEMIM TERRITORI				
	I - Punime rrethimi				
2.5	Germim e mbushje dheu me krah kategoria III per themele, h = 1.5m	m3	30.5		
2.114/1	Plinta e themele b/a monolite deri 20 m3 C - 16/20	m3	26.8		
2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m	m3	0.9		
2.129/1	Mure b/a t = 11 ~ 20 cm, C 16/20, h ~ 4 m	m3	32		
2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.86		
2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.08		
2.413	F.V zgara dekorativa hekuri me figuracion mesatare dritare	ton	4.1		
2.404/1	Boje hidroplastike importi cilesi e I-re jasht	m2	339		
2.401	Boje vaji sipërfaqe metalik	m2	244		
	Shuma - 1	leke			
	2 - Punime sistemim sheshi				
An2.413	Hegje konstruksion metalik rrethimi	ton	3.6		
2.426	Prishje mur tulle pa pastrim	m3	36		
2.260	Germim themele e plinta b>2m, ekskavator me goma, kova 0.25m3 shkarkim auto	m3	406		
2.37/5a	Transport mbeturina ndertimi me auto deri ne 5 km	m3	1060		
2.258	Nenshtrese zhavori 15cm	m3	109		
An2.262/4	Shtrese betoni C 16/20 me ngjyra	m3	46.5		
2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	2.3		
3.620	Shtresa, me 6 cm beton, me pllaka rruga e hyrjes	m2	418		
Analize	Sistemim, punim, nivelim dhe pasurim dheu me humus 15kg/m2	m2	628		
3.643	Mbjellje bari ne skarpat	m2	628		
3.An-164	F.V Peme dekorative	cope	25		
An168	F.V.shkurre dekorative Juniperus V.18 grup 3 cdo 6.6M	cope	65		
	Shuma - 2	leke			
	SHUMA - V				

VI - MOBILIMI URBAN				
1 - Punime te amfiteatrit				
2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20 amfiteatri	m3	8.4	
2.239/a	Shtrese me polisterol per mbushje	m3	6.4	
2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.41	
2.282	Shtrese derrasa FM 4.0cm	m2	10	
2.403	Boje vaji mbi sipërfaqe te patinuar	m2	36	
2.400	Boje vaji sipërfaqe druri	m2	13.6	
Shuma - 1		leke		
2 - Stolat 3 ML (Per nje stol)				
2.5	Germim e mbushje dheu me krah kategoria III per themele, h = 1.5m	m3	0.18	
2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20 amfiteatri	m3	0.49	
2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.03	
2.282	Shtrese derrasa FM 4.0cm	m2	1.2	
2.403	Boje vaji mbi sipërfaqe te patinuar	m2	4.31	
2.400	Boje vaji sipërfaqe druri	m2	3.63	
Shuma		leke		
Shuma - 2 (per 8 cope stola 3 ML)		leke	8	
3 - Stolat 1,8 ML (Per nje stol)				
2.5	Germim e mbushje dheu me krah kategoria III per themele, h = 1.5m	m3	0.04	
2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20 amfiteatri	m3	0.33	
2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.02	
2.282	Shtrese derrasa FM 4.0cm	m2	0.72	
2.403	Boje vaji mbi sipërfaqe te patinuar	m2	2.92	
2.400	Boje vaji sipërfaqe druri	m2	2.19	
Shuma		leke		
Shuma - 3 (per 12 cope stola 1,80M)		leke	12	
4 - Tavolina (Per nje tavoline)				
2.5	Germim e mbushje dheu me krah kategoria III per themele, h = 1.5m	m3	0.04	
2.114/1	Plinta e bazamente b/a monolite deri 20 m3 C - 16/20 amfiteatri	m3	0.44	
2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.02	
2.282	Shtrese derrasa FM 4.0cm	m2	9.1	
2.403	Boje vaji mbi sipërfaqe te patinuar	m2	4.3	
2.400	Boje vaji sipërfaqe druri	m2	27	
Shuma		leke		
Shuma - 4 (per 6 cope tavolina)		leke	6	
SHUMA - VI				

VII-PUNIME HIDROSANITARE + MKZ					
2.504	F.V.WC allaturka	cope	19		
2.495	F.V.lavaman me kollone me mishelator	cope	29		
2.An 149	F.V Kabine dushi 80 x 80 cm e thjeshte	cope	2		
2,515.000	F.V.pilete O 50 mm	cope	4		
2.519	Tub kanalizimi pvc Ø 75 mm (kollonat e ajrimit)	ml	30		
2,491/h	F.V.tubo plastike pvc 110 mm	ml	30		
2,491/i	F.V.tubo plastike pvc 125 mm	ml	15		
2.491/k	F.V Tuba plastike kurrogato d=200mm, (derdhja e jashtme e kanalizimeve)	ml	60		
2,491/f	F.V.tubo plastike pvc 63 mm	ml	20		
2.491/c	F.V Tuba e rakorderi ujesjellesi PPR d=20~32mm, PN 16	ml	120		
2/91An10	F.V. sarcineska 3/4'	cope	6		
2/91An10	F.V. sarcineska 1/2'	cope	1		
2/91An10	F.V. sarcineska 2"	cope	3		
2.An - 21	Pusete shkarkimi b/a, 80 x 80 cm, h = 200 cm	cope	5		
2.261	Shtrese rere	m3	28		
2.100	Germim dheu me krahe e transport me k dore 10 m, kategoria III(tubot Φ-200)	m3	30		
2.492	F.V tub xingato dhe rakorderi Ø -2 "	kg	60		
2.510	F.V kasete+ hidrante Ø 50 mm(me markuc najloni 25m)	cope	3		
An	F.V.Tubo xingato 1/2"+ rakorderi	ml	30		
An	F.V.Tubo xingato 1 1/4"+ rakorderi	ml	20		
2.494/3	F.V saracineska bronzi Ø 1 1/4 "= 32 mm	cope	1		
An	Koka sprinkleri G5 STANDART RESPONSE	cope	5		
2.512	F.V hidrante Ø 100 mm i jashtem	cope	1		
An	Shuars te thate kategoria A,B, C, D, E 6 kg	cope	50		
2.An - 11	F V rezervuari zingato 5000 litra	cope	2		
2.An - 13	F V rezervuari zingato 1000 litra	cope	3		
2.An - 17	F V pompe me pulmon 24 litra	cope	2		
An-13	Shpim pusi 60 m komplet+aksesore	cope	1		
Shuma - VII		leke			
VIII - PUNIME ELEKTRIKE					
I - Punime elektrike godina e shkolles					
2. a-127	Ndricules fluoreshent 2x36w,IP40	cope	224		
2. a-136	Ndricules pllafonier muror ndricim i jashtem 1x60w	cope	18		
2.485/3	F.V Çeles 1 polar 220V 10A Ticino"	cope	62		
2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	1841		
2.482/1	F.V percjelles PPV, Ø 2 x 1.5 mm2	ml	370		

2. a-104	Automat termo-elektro magnetik, 4P; 380V; 100A	cope	3		
480/3	F.V tub plastmasi Ø 22 ~ 26 mm	ml	1660		
2.490	F.V kuader ndriçimi	cope	3		
2.490/1b	F.V Automat termo/el.manj. diferencial 2P 220V, 16A	cope	26		
2.490/1d	F.V Automat termo/el.manj. diferencial 2P 220V, 40A	cope	8		
2.490/d	F.V Kasete plastike KE me 23 modular (vende)	cope	3		
2. a-120	Llampe sinjalizimi 220V; 1.2w	cope	9		
2.487/d	F.V kuti suport "Celsa Prizash" pllaket 4 modular Gevis	cope	291		
2.481/2	F.V percjelles PV-500 Ø 2.5 mm ²	ml	3640		
2. a-110	Panel shperndares ne Tension te Ulet, komplet me 1 Automat 380V, 4P, 330A + 3 Automate 380V, 4P, 250A	cope	1		
2.485/b	F.V priza bivalente 220V 10A 2P-T Gevis	cope	291		
2. a-131	Ndricues tip plafoniere, emergjence, 1x18w, IP65 tek shkallet	cope	6		
2.481/3	F.V percjelles PV-500 Ø 4 mm ²	ml	326		
2.481/4	F.V percjelles PV-500 Ø 6 mm ²	ml	420		
2.487	F.V Kutiderivacioni plastike	cope	63		
An	Dektor Tymi	cope	81		
2. a-121	Kanaline metalike 150x50	cope	12		
4.133/3.7	F.V ne toke kablllo Al fuqie me izolim gome 4x25mm ²	m	50		
2. a-116	Sirene e brendshme audio vizive	cope	6		
	Shuma - 1	leke			
	2 - Punime elektrike palestres				
2.481/4	F.V percjelles PV-500 Ø 6 mm ²	ml	420		
480/3	F.V tub plastmasi Ø 22 ~ 26 mm	ml	130		
2.490/1	F.V Automat termo/el.manj. diferencial 2P 220V, 32A, dl=0.03A	cope	2		
2.490/b	F.V Kasete plastike KE me 6 modular (vende)	cope	1		
2. a-129	Ndricues projektor me llampe SAP-T 250w	cope	8		
	Shuma - 2	leke			
	3 - Punime Interneti				
480/2	F.V tub plastmasi Ø 18 ~ 21 mm	ml	480		
-2,482/1	F.V percjelles interneti UTP	ml	620		
2,485/b	F.V priza interneti	cope	43		
2487/a+an	F.V kuti per priza interneti 1 modulshe jasht murit	cope	43		
	Shuma - 3	leke			
	4 - Punime elektrike ne oborr				

4.133/3.5	F.V ne toke kablllo Al fuqie +1000V,me izolim gome 4x16mm ²	ml	20		
4.133/3.5	F.V ne toke kablllo Al fuqie +1000V, gome 4x10mm ²	ml	90		
4.142/2.1	F.V kablllo CU pa armuar ,ne mure e konstruksioni 4x1.5mm ²	ml	50		
3.654	F.V tub plasmasi ϕ 100mm	m	100		
3.An/55	F.V Pusete elektrike kontrolli PVC 40x40x40cm	cope	6		
2.a-129	F.V ndricues projektor me llampe SAP-T 250W	cope	12		
2.481/2	F.V percjelles PV-500 \emptyset 4 mm ² . per togezimin nga shtylla ne shtylle	ml	100		
An	F.V Kuader komandimi komplet me santeri +fotoelement	cope	1		
2.a-93	Percjelles togezimi bakrri Cu,S=35mm ² I shveshur	m	6		
3.An/ksh	FV krah shtylla metalike KRH - MSI 1500/1500/10	cope	12		
An	F V shtylla dekorative dy degeshe ndriçim, H=8m,	cope	6		
3.An/et	F.V Elektrode togzimi te nxiguar L=150cm	cope	6		
2.490/1a	F.V Automat termo /el manj diferencial 220v, 10A	cope	6		
3.25/a	Germim me krahe seksion detyruar me gjeresi $b < 1$ m, h=1.5 m, toke e zak.	m ³	6		
2.553	F.V tub betoni ϕ 300ml	ml	3		
3.240.	Mbushje me beton marka 150 per ikastrim shtyllash	m ³	3		
3.An-56	F.V Tuba Metalike D=140mm	ml	6		
3.182/a	Shtrese rere natyrore t=10cm	m ²	4		
	Shuma - 4	leke			
	Shuma - VIII	leke			

IX - Ambjenti teknik I ngrohjes					
2.114/1	Plinta e bazamente b/a monolite deri 20 m ³ C - 16/20 (t=25cm), per vendosjen e depozitave	m ³	6		
2.493	F.V Tuba çeliku i zi	kg	550		
2.535/f	Termoizolim tubi \emptyset 1 1/2"me armofleks (d54x9)	ml	42		
2.535/d	Termoizolim tubi \emptyset 1 1/4"me armofleks (d42x9)	ml	38		
2.535/c	Termoizolim tubi \emptyset 1"me armofleks (d35x9)	ml	62		
2.535/b	Termoizolim tubi \emptyset 3/4"me armofleks (d28x9)	ml	40		
2.494/b	F.V tuba bakri e rakorderi d = 18x1 mm	ml	40		

2.494/c	F.V tuba bakri e rakorderi d = 22x1 mm	ml	62		
2.494/d	F.V tuba bakri e rakorderi d = 28x1.5 mm	ml	38		
2.494/e	F.V tuba bakri e rakorderi d = 35x1.5 mm	ml	42		
An/50	F.V. Tub çeliku i Preizoluar Ø 1½"	ml	58		
2.512/3	F.V Kolektor shpendares 3/4"(5+5)	cope	3		
2.512/5	F.V Kolektor shpendares 1"(6+6)	cope	3		
2.512/6	F.V Kolektor shpendares 1 1/4"(7+7; 8+8; 9+9)	cope	18		
2.494/a	F.V tuba bakri e rakorderi d = 15x1 mm (me termoizolim)	ml	3160		
An/52	F.V Rakorderi bakri(bryla,ti,reduksione) dhe element te nevojshem per montim	kompl	1		
An/53	F.V grup per mbushjen automatike me by-pass te integruar dhe me filter per impiantin e ngrohjes per linjat qarkulluese te mbyllura Ø 1/2"	cope	1		
An/54	F.V kanal per largimin e tymrave dy kanale,kanali I brendshem prejllamarine inoxi dhe kanali i jashtem me llamarin çeliku e galvanizuar, me strese termoizoluese. Me dimensione 220/250 mm .	ml	5		
An/55	F.V. Kolektoret prej tubi çeliku pa tegel per furnizimin e terminaleve ngrohjes ne dergim/kthimit DN 100 mm	shume	1		
An/56	F.V. Saraçeneska sferike me lidhje femer, standarte me dimensione DN 40, PN 6 Bar, Komfort normes EN 331	cope	8		
An/57	F.V. Saraçeneska sferike me lidhje femer, standarte me dimensione DN 32, PN 6 Bar, Komfort normes EN 331	cope	2		
An/58	F.V. Valvol moskthimi me gjuhez metalike , dimensione DN 40, PN 6 Bar, Komfort normes 0313EN	cope	1		
An/59	F.V. Filter e inspektueshme me dimensione DN 40, PN 6 Bar, Komfort normes 0329EN	cope	1		
An/60	F.V. Xhunto antivibrueseprej gome me dimensione DN 50 PN 6 bar	cope	2		
An/61	F.V. Valvol mishelatриçe tredegesh e pajisur me servomotorr dhe aksesoret perkates DN 50	cope	1		
An/62	F.V. termometer me zhytje,per matjen e temperatures ne dergim dhe rikthim me diapazon 0-120 °C	cope	5		

An/63	F.V. Manometer,per matjen e presionit te punes se linjave te sistemit te ngrohjes ne dergim dhe rikthim me diapazon matje 0-20bar	cope	5		
An/64	F.V. Ajernxjerres automatik me dimension Ø 1/2"	cope	15		
An/65	F.V. valvul sigurie per impiantin e ngrohjes,me presion pune 3 bar dhe lidhje 1/2"	cope	1		
An/66	F.V Rregullator klimaterik elektronik me mikroprocesor I pajisur me sensor temperature kabull komunikimi si dhe te gjitha aksesoret perkates	cope	1		
An/67	F.V. Valvul termorregulluese e pajisur me koke termostatike dhe me elementet e nevojshem per montim Ø 1/2"	cope	316		
An/68	F.V. valvul nderprerese per radiator,e kompletuar me te gjithe elementet e montimit Ø 1/2"	cope	316		
SHUMA IX					

SHUMA I+II+III+IV+V+VI+VII+VIII+IX		leke			
2 % Fondi rezerve					
Shuma I					94,196,68 4
20 % TVSH					
SHUMA A					

B- PAISJE TE NGROHJES					
An	F.V.Kaldaje me lende djegese Pellet / dru (MLC-BIO 300). Fuqia nominale: 349 kW PN; Rendimenti me Palles" 93% Kapaciteti I ujit: 169 litra;Lidhjet hidraulike: DN 40;Presioni i punes: 3 bar	kompl	1		
An	F.V. Sillos me material celiku, volumi 5m ³ , me materialin djeges, perfshire aksesoret e dergimit automatik	kompl	1		
An	F.V Radiator me 7 elemente, me llamarine 600x200 mm	cope	11		
An	F.V Radiator me 12 elemente, me llamarine 600x200 mm	cope	111		
An	F.V Radiator me 15 elemente, me llamarine 600x200 mm	cope	36		

An	F.V. Pompe Binjake per terminalet; V=3.5 m3/h, H=12mkH2O Lidhja hidraulike DN40, PN 10. E kompletuar me te gjitha rakorderite e nevojshme per instalim	cope	2		
An	F.V. Ene zgjerimi me kapacitet: V=80 lit, PN 10 Lidhja Hidraulike DN 20	cope	1		
An	Pompe e impiantit te mbrojtjes nga zjarri : V=2.1m3/h, H=35mkH2O. I kompletuar me te gjitha aksesoret e montimit	cope	1		
An	Pompe furnizimi per HS	cope	1		
An/79	Autoklave, V=200 l, P=10 bar, Lartesia=1065mm	cope	1		
An-11	F.V rezervuari zingato 5000 litra	cope	5		
	SHUMA - B (PAISJE)				11,151,480
	SHUMA (1) + SHUMA B				
	SHUMA TOTALE (A) + B				

Shenim: Te vlera e paisjeve te ngruhjes nuk aplikohet T.V.SH-ja

