



REPUBLIKA E SHQIPERISE

BASHKIA KAMEZ

Nr _____ Prot. _____

Kamez me _____ / _____ /2018

PREVENTIV

Ndertim Rruga Faik Konica , Rruga Fan Noli , Paskuqan 2 , Nj.Ad. Paskuqan , B. Kamez

Rruga Faik Konica Lt = 640 ml , L2= 260 m, B= 5 m Basfalt= 4 m+ kunete 2x0.5 m, Rruga Fan Noli L1=380 m, B= 7 ml, basf. 4.5 m, + kuneye 1x5 m bankine 2x1 m

NR	ANALIZ.	EMERTIMI I PUNIMIT	Njesi	Sasia	Çmimi	Vlefte
----	---------	--------------------	-------	-------	-------	--------

Objekti : NDERTIMI I RRUGES Fan Noli , PASKUQAN 2 Vreshte , Bashkia Kamez

Nr.	Nr.An.	Emërtimi i procesit të punës	Njësia	Sasia	Çmimi	Vlera - leke
I. Punime ne rrugen (Faik Konica) , degezime B= 5 m Basf= 4 + kunete 2x0.5 m L= 260 m						
1	2.426/2	Prishje mure ekzistuese me blloqe	m ³	68.0		-
2	3.139	Germim dheu ne trupin e rruges	m ³	260		-
3	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	260		-
4	3.158/5a	Transport Cakull me auto 5 km	m ³	260		-
5	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	1,300		-
6	3/212/6	Shtreses stabilizant t=10 cm	m ²	1,040		-
7	3.229/1	Shtrese binderi 5 cm + Sperkatje me emulsion	m ²	1,040		-
8	3.233/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	1,040		-
9	3.617/1	F.V bordura betoni 15x30 cm	ml	720		-
10	3.183/a	Shtrese zhavor lumi, nen themelin e bordures, t=10cm	m ²	198		-
11	3.238	Struktura monolite betoni, C 6/10, kundrabordura	m ³	136		-
12	3.158/5a	Transport dherash me auto 5 km	m ³	260		-
13	anal	Heqje dhe Montim Shtylla Elektrike (Kabllor+ tela)	cope	4		-
Punime KUB						
1	3.139	Germim dheu me eksavator	m ³	148		-
2	3.158.5a	Transport dheu me auto 5 km	m ³	148		-
3	3.353	Mbushje me cakull shkambi	m ³	49		-
4	3.158.5a	Transport cakull shkambi 5 km	m ³	49		-
5	3.An.1t	F.V. Tubo brinjerzuar ø 315 mm	ml	290		-
6	2.an.23	Puseta shiu me kapak gize 40x60, kapak gize	cope	16		-
7	2.262.4	Shtrese betoni per kunete	m ³	26		-
Shuma II						0

Objekti : NDERTIMI I RRUGES Fan Noli , PASKUQAN 2 Vreshte , Bashkia Kamez

Nr.	Nr.An.	Emërtimi i procesit të punës	Njësia	Sasia	Çmimi	Vlera - leke
II. Punime ne rrugen (Fan NOLI) , degezime B= 7 m Basf= 4.5 + kunete 1x0.5 m + bankine 2x1 m , L= 380 m						
1	2.426/2	Prishje mure ekzistuese me blloqe	m ³	160.0		-
2	3.139	Germim dheu ne trupin e rruges	m ³	474		-
3	3.353	Shtrese cakelli per profilim (Mbushje)	m ³	260		-
4	3.158/5a	Transport Cakull me auto 5 km	m ³	260		-
5	3.208	Shtrese çakelli t=10cm, makadam, perhapur e ngjeshur me makineri	m ²	2,660		-
6	3/212/6	Shtreses stabilizant t=10 cm	m ²	1,710		-
7	3.229/1	Shtrese binderi 5 cm + Sperkatje me emulsion	m ²	1,710		-
8	3.233/1	Shtrese asfalto betoni 4 cm + Sperkatje me emulsion	m ²	1,710		-

9	3.617/1	F.V bordura betoni 15x30 cm	ml	720		
10	3.183/a	Shtrese zhavor lumi, nen themelin e bordures, t=10cm	m ²	345		
11	3.238	Struktura monolite betoni, C 6/10, kundrabordura	m ³	20		
12	3.158/5a	Transport dherash me auto 5 km	m ³	474		-
13	anal	Hegje dhe Montim Shtylla Elektrike (Kabllo+ tela)	cope	6		-
		Punime KUB				
1	3.139	Germim dheu me eksavator	m ³	190		
2	3.158.5a	Transport dheu me auto 5 km	m ³	190		
3	3.353	Mbushje me cakull shkambi	m ³	91		
4	3.158.5a	Transport cakull shkambi 5 km	m ³	91		
5	3.An.1t	F.V. Tubo brinjzuar ø 315 mm	ml	380		
6	2.an.23	Puseta shiu me kapak gize 40x60, kapak gize	cope	13		
7	2.262.4	Shtrese betoni per kunete	m ³	19		
		Shuma II				
		III. Ndertim Trotuari te Rruges 2x1.25				
1	3.353	Mbushje me zhavorr per bankine (t=20 cm)	m ³	144		
2	An	Ngritje Pusete KUZ (1x1x1.5)	cope	6		
		Shuma III				
		SHUMA B		I+II+III+IV+V		
		SHUMA A + B				
		T. V. SH.		20%		
		SHUMA				

Shenim: Preventivi eshte hartuar ne Baze te analizave te çmimeve me VKM nr.629 dt.15.07.2017

Preventivoi:

Ing.Hajredin MURGU

Ing. Flora MUÇA

Ing. Elmaz MURATI

DREJTORI P.K.ZH.T-SE

Ark.Arber TOLA

MIRATOI

Xhelal MZIU

K R Y E T A R