



OBJEKTI: ZGJATIM I RRUGES GURRE+RRUGA GJORICE,ZGJATIM I RRUGES DAJTI

L1=205ml Gurre, B=6m, basf=5m+0.5*2 bankine, Gjorice L2=140ml, B=6m, basf=5m+0.5*2 bankine

Nr	An.	Emertimi I Punimeve	Njesia	Sasia	Cmimi	Vlera
A		PUNIME NE RRUGE, L=205m				
1	3.139	Germim i dheut me eskavator me goma kat. III	m ³	61		
2	3.158/5a	Transport dheu me auto 5km	m ³	61		
3	3.353	Mbushje me cakull shkembor +bankine	m ³	123		
4	3.158/5a	Transport cakull me auto 5km	m ³	123		
5	3.208	Shtrese cakulli T=10cm+bankine	m ²	1230		
6	3.212/b	Shtrese stabilizanti t=10 cm+bankine	m ²	1230		
7	3.229/1	Shtrese binder t=5 cm	m ²	1025		
8	3.231/1	Shtrese asfaltobetoni t=4 cm	m ²	1025		
9	An.	Ngritje pusete	cope	4		
10	An.	Spostim shtylla centrifugale betoni	cope	2		
11	An.96	Tabele sinjalistike 60-90cm	cope	2		
		SHUMA I				
II		PUNIME NE RRUGE, L=140m				
1	3an.43	Skarifikim asfalti	m ²	700		
2	3.353	Mbushje me cakull shkembor +bankine	m ³	14		
3	3.158/5a	Transport cakull me auto 5km	m ³	14		
4	3.229/1	Shtrese binder t=5 cm	m ²	140		
5	3.231/1	Shtrese asfaltobetoni t=4 cm	m ²	700		

6	An.96	Tabele sinjalistike 60-90cm	cope	2		
		SHUMA II				
		SHUMA A				

OBJEKTI: ZGJATIM I RRUGES DAJTI ME RRUGEN ARGJINATURE

L=280ml, B=6m $b_{ast}=5m+0.5*2$ bankine						
Nr	An.	Emertimi I Punimeve	Njesia	Sasia	Cmimi	Vlera
B		PUNIME NE RRUGE				
1	3.139	Germim i dheut me eskavator me goma kat. III	m ³	84		
2	3.158/5a	Transport dheu me auto 5km	m ³	84		
3	3.353	Mbushje me cakull shkembor +bankine	m ³	252		
4	3.158/5a	Transport cakull me auto 5km	m ³	252		
5	3.208	Shtrese cakulli T=10cm+bankine	m ²	1680		
6	3.212/b	Shtrese stabilizanti t=10 cm+bankine	m ²	1680		
7	3.229/1	Shtrese binder t=5 cm	m ²	1400		
8	3.231/1	Shtrese asfaltobetoni t=4 cm	m ²	1400		
9	An.	Ngritje pusete	cope	4		
10	An.	Spostim shtylla centrifugale betoni	cope	2		
11	An.96	Tabele sinjalistike 60-90cm	cope	2		
		SHUMA B				

OBJEKTI: Seg. qe lidh Rrugen "Zana" me Rrugen "Demokracia"

L=85ml, B=3m $b_{ast}=3m$						
Nr	An.	Emertimi I Punimeve	Njesia	Sasia	Cmimi	Vlera
C		PUNIME NE RRUGE				
1	3.139	Germim i dheut me eskavator me goma kat. III	m ³	13		
2	3.158/5a	Transport dheu me auto 5km	m ³	13		
3	3.353	Mbushje me cakull shkembor+bankine	m ³	26		
4	3.158/5a	Transport cakull me auto 5km	m ³	26.0		
5	3.208	Shtrese cakulli T=10cm +bankine	m ²	255		
6	3.212/b	Shtrese stabilizanti t=10 cm +bankine	m ²	255		
7	3.229/1	Shtrese binder t=5 cm	m ²	255		
8	3.231/1	Shtrese asfaltobetoni t=4 cm	m ²	255		
9	An.	Ngritje pusete	cope	1		

10	2.426/2	Prishje mure blloqe + transport	m³	51		
11	An.96	Tabele sinjalistike 60-90cm	cope	2		
12	2/110/2	Mure betoni + bordura anesore e pergatitur ne vend	m³	26		
		SHUMA C				
		SHUMA A+B+C				
		T.V.SH 20%				
		SHUMA TOTALE				

Preventivues:

Ing. Elmaz MURATI
Ing. Flora MUÇA
Ing. Hajredin MURGU

Drejtori i P.K.ZH.T-se

Ark.Arber Tola

MIRATOI
Xhelal MZIU

K R Y E T A R