

Preventivat perkates per sa me sipër paraqiten ne tabelat e meposhtme:

A. Baza Materiale

PREVENTIV A

Instalim panel matje intiligjente me transformator rryme , ne T.U.

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlera
	A - MATERIALE				
1	<i>1 - KABLO PER URA TRANSFORMATORI T.U.</i>				
1.1	Kabell T.U. XLPE AL - 4x50 mm ²	ml	224		
1.2	Kabell AL-XLPE 0.6/1 kV (1x150mm ²)	ml	12000		
1.3	Kabell AL XLPE 0.6/1 kV (1x240mm ²)	ml	28400		
	SHUMA 1				
2	<i>2 - PANEL MATJE TU ME TRI PER VENDOSJE BRENDA</i>				
2.1	Me TRI 100/5 A, perfshire data koncentror dhe mates smart	cope	6		
2.2	Me TRI 200/5 A, perfshire data koncentror dhe mates smart	cope	84		
2.3	Me TRI 300/5 A, perfshire data koncentror dhe mates smart	cope	96		
2.4	Me TRI 400/5 A, perfshire data koncentror dhe mates smart	cope	324		
2.5	Me TRI 600/5 A, perfshire data koncentror dhe mates smart	cope	14		
2.6	Me TRI 800/5 A, perfshire data koncentror dhe mates smart	cope	1012		
2.7	Me TRI 1000/5 A, perfshire data koncentror dhe mates smart	cope	60		
	SHUMA 2		1596		
3	<i>3 - PANEL MATJE TU ME TRI PER VENDOSJE JASHTE</i>				
3.1	Me TRI 100/5 A, perfshire data koncentror dhe mates smart	cope	22		
3.2	Me TRI 200/5 A, perfshire data koncentror dhe mates smart	cope	580		
3.3	Me TRI 300/5 A, perfshire data koncentror dhe mates smart	cope	103		
3.4	Me TRI 400/5 A, perfshire data koncentror dhe mates smart	cope	94		
3.5	Me TRI 600/5 A, perfshire data koncentror dhe mates smart	cope	23		
	SHUMA 3		822		

4	4 - MATESAT SMART DHE KONCENTRATORET DCU				
4.1	Mates energjie smart 3x230/400V 5(6)A	cope	932		
4.2	Koncentrator te dhenash 3x230/400V 5(6)A	cope	932		
	SHUMA 4		932		
5	Upgrade dhe Integrim i platformes HES				
5.1	Upgrade i sistemit HES (Head End Sytem) dhe integrimi i matesave +DCU	set	1		
5.2	Training Package Operation and Maintenance of Communication Units, HES	set	1		
5.3	Test and Inspection of outdoor and indoor Meter Panel, Smart Meters, Communication Units, HES	set	1		
5.4	Commissioning and Operational Acceptance of outdoor and indoor Meter Panel, Smart Meters, Communication Units, HES	set	1		
	SHUMA 5				
	SHUMA TOTALE A	cope	3350		

B. Puntori

PREVENTIV B

Instalim panel matje intilgjente me transformator rryme , ne T.U.

Nr.	Analize	Emertimi	Njesia	Sasia	Çmimi	Vlera
		B - PUNTORI				
6		5 - PUNIME DEMONTIM - MONTIM -F.V. PER INSTALIMIN E PANELEVE TE MATJES VENDOSJE BRENDIA				
6.1	An 100A /B	Panel matje me TRI 100/5A perfshire mates smart dhe koncentrator	cope	6		
6.2	An 200A /B	Panel matje me TRI 200/5A perfshire mates smart dhe koncentrator	cope	84		
6.3	An 300A /B	Panel matje me TRI 300/5A perfshire mates smart dhe koncentrator	cope	96		
6.4	An 400A /B	Panel matje me TRI 400/5A perfshire mates smart dhe koncentrator	cope	324		
6.5	An 600A /B	Panel matje me TRI 600/5A perfshire mates smart dhe koncentrator	cope	14		
6.6	An 800A /B	Panel matje me TRI 800/5A perfshire mates smart dhe koncentrator	cope	1012		
6.7	An 1000A /B	Panel matje me TRI 1000/5A perfshire mates smart dhe koncentrator	cope	60		
6.8	smart	Matesa smart + koncentrator	cope	932		
		SHUMA 5				
7		5 - PUNIME DEMONTIM - MONTIM -F.V. PER INSTALIMIN E PANELEVE TE MATJES VENDOSJE JASHTE				
7.1	An 100A /J	Panel matje me TRI 100/5A perfshire mates smart dhe koncentrator	cope	22		

7.2	An 200A /J	Panel matje me TRI 200/5A perfshire mates smart dhe koncentrator	cope	580		
7.3	An 300A /J	Panel matje me TRI 300/5A perfshire mates smart dhe koncentrator	cope	103		
7.4	An 400A /J	Panel matje me TRI 400/5A perfshire mates smart dhe koncentrator	cope	94		
7.5	An 600A /J	Panel matje me TRI 600/5A perfshire mates smart dhe koncentrator	cope	23		
		SHUMA 6				
		SHUMA B				
		Fond rezerve 5%				
		SHUMA TOTALE B				

	SHUMA TOTALE A	ALL	
	SHUMA TOTALE B	ALL	
	SHUMA TOTALE	ALL	

PREVENTIV 6.1

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 100/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE BRENDA

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU - AL (4x50) mm ² ne grapeta	ml	8		
2	Shtrim kabell me grapeta XLPE AL - (4x50) mm ²	ml	4		
3	F.V. - Grapeta per fiksime kablli	cope	7		
4	V. - Shtrim kabell me grapeta XLPE AL - (4x50) mm ²	ml	8		
5	F.V. - Pergatitje kokash teli me presim (10 - 50) mm ²	cope	16		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (4x50) mm ²	cope	4		
7	Montim panel matje me TRI 100 /5A	cope	1		
8	Demontim matesi ekzistues	cope	1		
9	Demontim transformator rryme deri 200/5A		3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 200A		4		
11	F.V - Tokezim paneli TU 100/5 A , (lidhje me tokezimin e kabines)	"	1		
12	Matje izolacioni koke kablli + kablli me megaometer	"	8		
13	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.05		
	Shuma	leke			

PREVENTIV 6.2

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 200/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE BRENDA

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL - (1x150) mm ²	ml	32		
2	Shtrim kabell T.U XLPE AL - (1x150) mm ² ne grapeta	ml	16		

3	F.V. - Grapeta per fiksime kablli	cope	40		
4	V. - Shtrim kabell me grapeta XLPE AL - (1x150) mm ²	ml	30		
5	F.V. - Pergatitje kokash teli me presim (150 - 240) mm ²	cope	16		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (150-240) mm ²	cope	16		
7	Montim panel matje me TRI 200 /5A	cope	1		
8	Demontim matesi ekzistues	cope	1		
9	Demontim transformator rryme deri 1000/5A		3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 200A		4		
11	F.V - Tokezim paneli TU 200/5 A , (lidhje me tokezimin e kabines)	"	1		
12	Matje izolacioni koke kablli + kablli me megaometer	"	8		
13	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.06		
Shuma		leke			

PREVENTIV 6.3

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 300/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE BRENDA

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL - (1x150) mm ²	ml	32		
2	Shtrim kabell T.U XLPE AL - (1x150) mm ² ne grapeta	ml	16		
3	F.V. - Grapeta per fiksime kablli	cope	40		
4	V. - Shtrim kabell me grapeta XLPE AL - (1x150) mm ²	ml	30		
5	F.V. - Pergatitje kokash teli me presim (150 - 240) mm ²	cope	16		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	16		
7	Montim panel matje me TRI 300 /5A	cope	1		
8	Demontim matesi ekzistues	cope	1		
9	Demontim transformator rryme deri 1000/5A		3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 600A		4		
11	F.V - Tokezim paneli TU 300/5 A , (lidhje me tokezimin e kabines)	"	1		
12	Matje izolacioni koke kablli + kablli me megaometer	"	8		
13	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.08		
Shuma		leke			

PREVENTIV 6.4

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 400/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE BRENDA

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL 1x240 mm ²	ml	32		
2	Shtrim kabell T.U XLPE AL - (1x240) mm ² ne grapeta	ml	16		

3	F.V. - Grapeta per fiksime kablli	cope	20		
4	V. - Shtrim kabell me grapeta XLPE AL - (1x240) mm ²	ml	16		
5	F.V. - Pergatitje kokash teli me presim (150 - 240) mm ²	cope	16		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	16		
7	Montim panel matje me TRI 400 /5A	cope	1		
8	Demontim matesi ekzistues	cope	1		
9	Demontim transformator rryme deri 1000/5A		3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 600A		4		
11	F.V - Tokezim paneli TU 400/5 A , (lidhje me tokezimin e kabines)	"	1		
12	Matje izolacioni koke kablli + kablli me megaometer	"	8		
13	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.1		
Shuma		leke			

PREVENTIV 6.5

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 600/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE BRENDA

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL (1x150+1x240 mm ²)	ml	64		
2	Shtrim kabell T.U XLPE AL - (1x150+1x240) mm ² ne grapeta	ml	32		
3	F.V. - Grapeta per fiksime kablli	cope	40		
4	V. - Shtrim kabell me grapeta XLPE AL - (1x240) mm ²	ml	16		
5	V. - Shtrim kabell me grapeta XLPE AL - (1x150) mm ²	ml	16		
6	F.V. - Pergatitje kokash teli me presim 240 mm ²	cope	16		
7	F.V. - Pergatitje kokash teli me presim 150 mm ²	cope	16		
8	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	32		
9	Montim panel matje me TRI 600 /5A	cope	1		
10	Demontim matesi ekzistues	cope	1		
11	Demontim transformator rryme deri 1000/5A	cope	3		
12	F.V.- Pjaster Sekondari Tr.Fuqise Cu 600A		4		
13	F.V - Tokezim paneli TU 600/5 A , (lidhje me tokezimin e kabines)	"	1		
14	Matje izolacioni koke kablli + kablli me megaometer	"	16		
15	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.12		
Shuma		leke			

PREVENTIV 6.6

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 800/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE BRENDA

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL 1x240 mm ²	ml	64		
2	Shtrim kabell T.U XLPE AL - (1x240) mm ² ne grapeta	ml	32		

3	F.V. - Grapeta per fiksim kablli	cope	40		
4	F.V. - Shtrim kabell me grapeta XLPE AL - (1x240) mm ²	ml	32		
5	F.V. - Pergatitje kokash teli me presim 240 mm ²	cope	16		
6	F.V. - Pergatitje kokash teli me presim 150 mm ²	cope	16		
7	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	32		
8	Montim panel matje me TRI 800 /5A	cope	1		
9	Demontim matesi ekzistues	cope	1		
10	Demontim transformator rryme deri 1000/5A		3		
11	F.V.- Pjaster Sekondari Tr.Fuqise Cu 1000A		4		
12	F.V - Tokezim paneli TU 100/5 A , (lidhje me tokezimin e kabines)	"	1		
13	Matje izolacioni koke kablli + kablli me megaometer	"	16		
14	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.15		
Shuma B		leke			

PREVENTIV 6.7

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 1000/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE BRENDA

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL (1x150+1x240 mm ²)	ml	96		
2	Shtrim kabell T.U XLPE AL - (1x150+1x240) mm ² ne grapeta	ml	48		
3	F.V. - Grapeta per fiksim kablli	cope	40		
4	F.V. - Shtrim kabell me grapeta XLPE AL - (1x240) mm ²	ml	32		
5	F.V. - Pergatitje kokash teli me presim 240 mm ²	cope	32		
6	F.V. - Pergatitje kokash teli me presim 150 mm ²	cope	16		
7	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	48		
8	Montim panel matje me TRI 1000 /5A	cope	1		
9	Demontim matesi ekzistues	cope	1		
10	Demontim transformator rryme deri 1000/5A	cope	3		
11	F.V.- Pjaster Sekondari Tr.Fuqise Cu 1000A		4		
12	F.V - Tokezim paneli TU 100/5 A , (lidhje me tokezimin e kabines)	"	1		
13	Matje izolacioni koke kablli + kablli me megaometer	"	24		
14	Transport materiale ndertimi me auto deri 10.0 km	ton/km	1.7		
Shuma		leke			

PREVENTIV 6.8

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E MATES SMART + KONCENTRATOR

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL - 150-240 mm ²	ml	16		
2	Shtrim kabell T.U XLPE AL 150-240 mm ² ne grapeta	ml	8		
3	F.V. - Grapeta per fiksim kablli	cope	13		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	8		

1	Demontim matesi ekzistues	cope	1		
2	Montim mates energjie smart	cope	1		
3	Montim koncentrator te dhenash	cope	1		
11	Matje izolacioni koke kablli + kablli me megaometer	"	8		
12	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.005		
Shuma		leke			

PREVENTIV 7.1

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 100/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE JASHTE

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefta
1	Demontim kabell TU - AL (4x50) mm ² ne grapeta	ml	8		
2	Shtrim kabell me grapeta XLPE AL - (4x50) mm ²	ml	4		
3	F.V. - Grapeta per fiksime kablli	cope	7		
4	V. - Shtrim kabell me grapeta XLPE AL - (4x50) mm ²	ml	8		
5	F.V. - Pergatitje kokash teli me presim (10 - 50) mm ²	cope	16		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (4x50) mm ²	cope	4		
7	Montim panel matje me TRI 100 /5A	cope	1		
8	Demontim matesi ekzistues	cope	1		
9	Demontim transformator rryme deri 1000/5A		3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 200A		4		
10	F.V - Tokezim paneli TU 100/5 A , (lidhje me tokezimin e kabines)	"	1		
11	Matje izolacioni koke kablli + kablli me megaometer	"	8		
12	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.05		
13	Konstruksion metalik per trafo deri ne 250 kVA	cope	0.034		
Shuma		leke			

PREVENTIV 7.2

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 200/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE JASHTE

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefta
1	Demontim kabell TU AL - (1x150) mm ²	ml	32		
2	Shtrim kabell T.U XLPE AL - (1x150) mm ² ne grapeta	ml	16		
3	F.V. - Grapeta per fiksime kablli	cope	40		
4	V. - Shtrim kabell me grapeta XLPE AL - (1x150) mm ²	ml	30		
5	F.V. - Pergatitje kokash teli me presim (150 - 240) mm ²	cope	16		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	16		
7	Montim panel matje me TRI 200 /5A	cope	1		
8	Demontim matesi ekzistues	cope	1		

9	Demontim transformator rryme deri 1000/5A	cope	3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 200A	cope	4		
10	F.V - Tokezim paneli TU 200/5 A , (lidhje me tokezimin e kabines)	"	1		
11	Matje izolacioni koke kablli + kablli me megaometer	"	8		
12	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.06		
13	Konstruksion metalik per trafo deri ne 250 kVA	ton	0.034		
Shuma		leke			

PREVENTIV 7.3

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 300/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE JASHTË

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL - (1x150) mm ²	ml	32		
2	Shtrim kabell T.U XLPE AL - (1x150) mm ² ne grapeta	ml	16		
3	F.V. - Grapeta per fiksime kablli	cope	40		
4	V. - Shtrim kabell me grapeta XLPE AL - (1x150) mm ²	ml	30		
5	F.V. - Pergatitje kokash teli me presim (150 - 240) mm ²	cope	16		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	16		
7	Montim panel matje me TRI 300 /5A	cope	1		
8	Demontim matesi ekzistues	cope	1		
9	Demontim transformator rryme deri 1000/5A		3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 600A		4		
10	F.V - Tokezim paneli TU 300/5 A , (lidhje me tokezimin e kabines)	"	1		
11	Matje izolacioni koke kablli + kablli me megaometer	"	8		
12	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.08		
13	Konstruksion metalik per trafo deri ne 250 kVA	ton	0.034		
Shuma		leke			

PREVENTIV 7.4

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 400/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE JASHTË

Nr.	Emertimi	Njesia	Sasia	Çmimi	Vlefte
1	Demontim kabell TU AL 1x240 mm ²	ml	32		
2	Shtrim kabell T.U XLPE AL - (1x240) mm ² ne grapeta	ml	16		
3	F.V. - Grapeta per fiksime kablli	cope	20		
4	V. - Shtrim kabell me grapeta XLPE AL - (1x240) mm ²	ml	16		
5	F.V. - Pergatitje kokash teli me presim (150 - 240) mm ²	cope	16		
6	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	16		
7	Montim panel matje me TRI 400 /5A	cope	1		
8	Demontim matesi ekzistues	cope	1		

9	Demontim transformator rryme deri 1000/5A		3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 600A		4		
10	F.V - Tokezim paneli TU 400/5 A , (lidhje me tokezimin e kabines)	"	1		
11	Matje izolacioni koke kablli + kablli me megaometer	"	8		
12	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.1		
13	Konstruksion metalik per trafo deri ne 250 kVA	cope	0.034		
Shuma		leke			

PREVENTIV 7.5

PUNIME DEMONTIM -MONTIM -F.V. PER INSTALIMIN E PANEL MATJE ME TRI 600/5A PERFSHIRE MATES SMART + KONCENTRATOR VENDOSJE JASHTË

<i>Nr.</i>	<i>Emertimi</i>	<i>Njesia</i>	<i>Sasia</i>	<i>Çmimi</i>	<i>Vlefte</i>
1	Demontim kabell TU AL (1x150+1x240 mm ²)	ml	64		
2	Shtrim kabell T.U XLPE AL - (1x150+1x240) mm ² ne grapeta	ml	32		
3	F.V. - Grapeta per fiksime kablli	cope	40		
4	V. - Shtrim kabell me grapeta XLPE AL - (1x240) mm ²	ml	16		
5	V. - Shtrim kabell me grapeta XLPE AL - (1x150) mm ²	ml	16		
6	F.V. - Pergatitje kokash teli me presim 240 mm ²	cope	16		
7	F.V. - Pergatitje kokash teli me presim 150 mm ²	cope	16		
8	F.V. - Pergatitja e koka thata, kablllo te fuqise (150x240) mm ²	cope	32		
9	Montim panel matje me TRI 600 /5A	cope	1		
10	Demontim matesi ekzistues	cope	1		
11	Demontim transformator rryme deri 1000/5A	cope	3		
10	F.V.- Pjaster Sekondari Tr.Fuqise Cu 600A		4		
12	F.V - Tokezim paneli TU 600/5 A , (lidhje me tokezimin e kabines)	"	1		
13	Matje izolacioni koke kablli + kablli me megaometer	"	16		
14	Transport materiale ndertimi me auto deri 10.0 km	ton/km	0.12		
15	Konstruksion metalik per trafo deri ne 250 kVA	cope	0.057		
Shuma		leke			