



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

MIRATOI:
Kryetari
Z. Rakip SULI

Objekti : “NDERTIMI I PEDONALES DHE ZONAVE REKREATIVE TE PARKUT TE LIQENIT PASKUQAN”

Nr	An	EMERTIMI I PUNIMEVE	NJESIA	SASIA	CMIMI	VL
II-PUNIME GERMIMI						
1	3.104/b	Germim dheu me ekskavator zinxhir, 0.5 m ³ , ne kanale	m ³	9253		0
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	9253		0
SHUMA I						0
III-PUNIME SHITRESASH						
1	An.	Kompaktim per permiresimin e parametrave peshemnajtese	m ²	258		0
2	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	18860		0
	3.212/b	Shtrese stabilizant t=10cm	m ²	18860		0
3	An.	Shtrese betoni C20/25 me beton te stampuar ne forme guri	m ²	12070.4		0
4	3.222/2	Shtrese binderi me granil gur kave, 6cm, me makineri	m ²	6318		0
5	3.226/1a	Shtrese asfaltbetoni me ngjyre me granil guri kave, 4cm,	m ²	6318		0
6	3.616	F V bordura betoni 12x25 cm	m	8344		0
SHUMA II						0
V - PUNIME PER VEPRAT E ARTIT						
Ura veriore						
1	2.181	Konstruksione metalike te perbera	ton	158		0
2	2.401	Boje vaji siperfaqe metalike	m ²	2075		0
3	3.247	Struktura monolite betoni me çakell C 25/30 per jasteket e	m ³	84		0
4	An SD2	Shpim me sonda ne toka te zakonshme Ø 800mm,	m	336		0
5	Analize 1	Krijim ishulli me dhe te hedhur per kryerjen e sondave	m ³	6750		0
6	3.247	Struktura monolite betoni me çakell C 25/30 per pilotat	m ³	84		0
7	Analize 2	Shtrese me derrase te komprimuar t = 3cm	m ²	780		0
8	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale	m ³	6750		0
9	2.37/3a	Transport materiale ndertimi, dheu me auto deri 3.0 km	m ³	6750		0

10	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	18.4		0
11	Analize 3	Largim i ujit me sistemin wellpoint	op	2500		0
12		Ura Jugore				0
13	2.181	Konstruksione metalike te perbera	ton	16.3		0
14	2.401	Boje vaji siperfaqe metalike	m ²	404		0
15	3.247	Struktura monolite betoni me çakell C 25/30 per jasteket e	m ³	5.76		0
16	An SD2	Shpim me sonda ne toka te zakonshme Ø 800mm,	m	64		0
17	3.247	Struktura monolite betoni me çakell C 25/30 per pilotat	m ³	24		0
18	Analize 2	Shtrese me derrase te komprimuar t = 3cm	m ²	180		0
		SHUMA III				0
		VI - PUNIME PER 2 PARKIMET PUBLIKE + RRUGA				
1	3.104/b	Germim dheu me ekskavator zinxhir, 0.5 m ³ , ne kanale	m ³	2844		0
2	3.243	Struktura monolite betoni C 16/20 per mure dhe bordura	m ³	185		0
3	3.212	Shtrese çakelli t=10/15cm, makadam, perhapur e ngjeshur	m ²	3998		0
	3.212/b	Shtrese stabilizant t=10cm	m ²	3998		0
4	An	Sperkatje me emulsion bituminoz 1 l/m ²	m ²	3998		0
5	3.229/3	Shtrese binderi me zall lavatrice, 7cm, me makineri	m ²	3998		0
6	3.233/1	Shtrese asfaltobetoni me zall lavatrice, 4cm, me mak	m ²	3998		0
7	3.62	Trotuar, me 6 cm beton, me pllaka	m ²	430		0
		SHUMA IV				0
		IV - PUNIME ELEKTRIKE				
		1. Pedonalja				
1	An.	F.V Tub corrugato Ø 63 mm	ml	4172		0
2	An.	F.V Pusete elektrike 20x20 cm	cp	263		0
3	Analize	Shpime horizontale me sonde per kalimin e rrjetit	ml	26		0
4		2. Kabllot				0
5	An.	F.V Kabell FG16OR 3x2.5mm	ml	4530		0
6	An.	F.V Kabell FG16OR 5x4mm	ml	3856		0
	An.	F.V Kabell FG16OR 5x6mm	ml	3874		0
	An.	F.V Kabell FG16OR 5x10mm	ml	2980		0
	An.	F.V Kabell FG16OR 5x16mm	ml	1750		0
8		3. Pajisjet				0
1	An.	V Shtylle e pajisur me ndriçues te lidhur me rrjetin dhe te	cope	263		0

10	An.	F.V Kuader elektrik i jashtem IP67	cope	2		0
11	3.An/et	F.V elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	95		0
		SHUMA V				0
VI - PUNIME SISTEMIMI						
1	3.5	Zhvendosje pemesh me makineri pa i demtuar dhe	cope	26		0
2	2.54/2	Mur guri per krijimin e strukturabe "Moongates", zonave	m ³	118		0
3	An.	Ndertim çezma betonarme me veshje me mur guri	cope	5		0
4	3.643	Mbjellje bari me tekniken e hidrombjelljes	m ²	1560		0
5	An163	F.V. Fidane Lule dekorative	cope	458		0
		SHUMA VI				0
VII-SINJALISTIKA						
1	An105	Tabela trekendore e vogel me A = 60	cope	12		0
2	An99	Tabele rrethi "detyrim" e vogel me D = 40	cope	12		0
3	An122	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm.	ml	475		0
4	An.	Pistona per ndalimin e qarkullimit ne pedonale	cope	4		0
		SHUMA VII				0
VIII-Punime KUB						
1	3.101/a	Germim dheu me ekskavator zingjir 0.5 m ³ , ne kanale	m ³	5751		0
2	3.158/1a	Transport dheu me auto deri 1.0 km	m ³	2875.5		0
3	3.244	Struktura monolite betoni C 20/25 per kanalin kullues	m ³	997		0
4	3.An/1t	F V tuba te brinjzuar HDPE SN8 d=315 mm	ml	586		0
5	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak gize	cope	39		0
		SHUMA VIII				0
		SHUMA I-VIII				0
		Fond rezerve 3%				0
		SHUMA				0
PAJISJET						
1	An.	F. Shtylle e pajisur me ndriçues te lidhur me rrjetin dhe te	cope	263		0
2	An.	Stola tip 2 dekorative (beton+ derrase)	cope	190		0
3	An.	Kosha mbeturinash Dekorativ	cope	100		0
		SHUMA PASJISJE				0
		SHUMA PA TVSH				0

		T.V.SH	20%			0
		TOTALI				0

V.O. Preventivi eshte hartuar ne baze te Vkm nr. 629 date 15.07.2015 + analizat perkatese

PREVENTIVOI

"TRIANGLE" sh.p.k

Drejtues Ligjor & Teknik

Ing. Zenulla MEHMETI