



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e znj.Zaire Shkurti ne fshatin Lapardha Njesia Administrative Otlak

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
1	An	Prishje suvatimi	m2	60		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	25		
		Shuma A				
		Punime ndertimore				
1	2.52/2	Mur guri themel e xokol me llaç perzier M 25	m3	13		
2	2.121/1	Brez b/a C 16/20, h ~ 8 m (antisizmik)	m3	2.15		
3	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m (antisizmike)	m3	5.5		
4	2.119/1a	Struktura b/a monolite C - 20/25, h ~ 4 m	m3	3		
5	2.64/2	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 25	m3	6.2		
6	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.55		
7	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.85		
8	2.310	Suva brenda murature me krah, llaç perzier M 25	m2	48		
9	2.219	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi (riparim)	m2	90		
10	3.375	Dritare d/alumini tek xham.	m2	4.7		
11	2.383/2	F V dyer druri importi cilesi e II-te.	m2	6.6		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e znj .Dallendyshe Troka ne fshatin Lapardha 1 ,Njesia Administrative Otlak

Nr.rend.	Nr.analize	Pershkrimi I punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje suvatimi	m2	120		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	11		
		Shuma A				
		Punime ndertimore				
1	2.64/1	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 15(mbyllje dhe rakordim te murit ekzistues me catine)	m3	2.3		
2	2.312	Suva brenda mur guri h=4m me krah, llaç perzier M 25	m2	68		
3	2.295	Tavan rrjete teli + suva	m2	72		
4	2.383/2	Fv dyer druri importi cilesi e II- te	m2	8.4		
5	3.375	Dritare d/alumini tek xham.	m2	4		
6	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	31		
7	2.326	Veshje me pllaka majolike	m2	5.4		
8	2.324/b	Plintuse grez importi .h= 10 cm	ml	20		
9	2.404	Boje hidroplastike	m2	80		
10	2.218	Çati vendi zakonshme HD-8m, mbuluar me tjegulla vendi	m2	90		
11	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	15		
12	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	12		
		Shuma B				
		Punime elektrike				
1	2.481/1	F.V. Percjelles 1.5 mm	ml	90		
2	2.481/2	F.V. Percjelles 2.5 mm	"	95		
3	2.480/3	F.V. Tuba plasmasi flek. Ø 26	"	95		
4	2.483	F.V. Çelesa 10 A	cope	7		
5	2.485	F.V. Priza 10 A me tokezim	cope	8		
6	2.487	F.v kuti devijacioni plastike	cope	2		
7	2.486	F,V Portollampa normale 10 A	cope	6		
8	2. a-120	Llampe sinjalizimi 220V;1.2w	cope	6		
9	2.490/d	F.V. Kuader (60 x 80 x 20) cm	cope	1		
		Shuma C				
		Shuma A+B+C				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



3



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Robert Hajdari ne fshatin Morave, Njesia Administrative Otlak

Nr.rend.	Nr.analize	Pershkrimi I punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
1	An	Prishje suvatimi dhe pastrim sipërfaqje murale	m2	70		
2	An	Pastrim I sipërfaqjes se taraces		82		
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	11		
		Shuma A				
		Punime ndertimore				
1	2.86	Mur me tulle me 6 vrima, t=12cm, h=3m, llaç perzier M15 (parapeti)	m3	3.8		
2	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k katrama (taraca)	m2	115		
3	2.300	Suva solete h ~ 4 m me drejtues, me krah	m2	115		
4	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	120		
5	2.310	Suva brenda mur tulle h=4m me krah, llaç perzier M 25	m2	90		
6	2.404	Boje hidroplastike	m2	120		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



2



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Gezim Hoxha ne fshatin Lapardha ,Njesia Administrative Odlak

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
1	A	Punime prishje				
	An	Prishje suvatimi	m2	42		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10,0 km	m3	13		
		Shuma A				
		Punime ndertimore				
1	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m	m3	1.2		
2	2.166	F.V hekur betoni periodik O 6 - 10 mm	ton	0.62		
3	2.167	F.V hekur betoni periodik O >10 mm	ton	0.9		
4	2.312	Suva brenda mur guri h=4m me krah, Ilaç perzjer M	m2	65		
		25	m2	43		
5	2.295	Tavan rreze tell + suva				
		Çati vendi zakonshme HD-8m, mbuluar me tjegulla	m2	78		
6	2.218	vendi				
		Shuma B				
		Shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Skender Bilcari ne fshatin Ullinjas Njesia Administrative Otllak

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmtimi	Vlera
A		Punime prishje e gërmimi Gërmim dheu me krah e transport me k dore 10 m.	m3	20		
1	2.1	Kategoria II	m2	40		
2	An	Prishje suvatime te brendshme	m3	25		
3	2.37/5b	Transport materiale ndërtimi, dheu me auto deni 10.0 km				
		Shuma A				
		Punime ndërtimore				
1	2.117/1	Strukture monolite 'b'a monolite C - 16/20, h ~ 4 m (perforcim themelesh dhe kolona)	m3	20		
2	2.166	F.V hekur betoni periodik Ø 6 - 10 mm	ton	1.2		
3	2.167	F.V hekur betoni periodik Ø > 10 mm	ton	0.8		
4	2.310	Suva brenda murature me krah, llaç perzier M 25	m2	50		
5	2.196	Hydroizolim me emulsion bitumi dhe 1 shtrese k kaltrama (laraca)	m2	65		
6	2.86	Mur me tullë me 6 vrime, t=12cm, h=3m, llaç perzier M15 (parapeti)	m3	2		
		Shuma B				
		shuma A+B				
		T.V.SH				
		Shuma totale				

Punoi
Ing.Valentina Karabina





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Tomor Baruti ne fshatin Bilce , Njesia Administrative Velabisht

Nr.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
1	A	Punime prishje				
	An	Prishje suvatimi	m2	130		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	1		
		Shuma A				
Punime ndertimore						
1	2.312	Suva brenda mur guri h~4m me krah, llaç perzier M 25	m2	185		
		Suva solete h ~ 4 m me drejtues, me krah	m2	98.75		
2	2.300	Dritare d/alumini tek xham.	m2	3		
3	2.375	F V dyer druri importi cilesi e II-te.	m2	7.4		
4	2.383/2	Shtrese me pilaka grez porcelanato	m2	80		
5	2.267/a	Plintuse grez importi, h = 10 cm	ml	90		
6	2.324/b	Veshje me pllake majolike	m2	22		
7	2.326	Boje hidroplastike	m2	185		
9	2.404	Hidroizolim me emulsion dhe dy duar bitumi dysHEMEJE /taraca	m2	190		
10	2.195	F.V WC alla turka importi	cope	1		
11	2.504	F.V bide importi porcelani	cope	1		
12	2.506	F.V tuba rakorderi ujesjellesi	ml	10		
13	2.491/a	F.V tub plastmasi Ø 22-26mm	ml	40		
14	480/3	F.V percjelles PV-500 Ø 1.5 mm2	ml	50		
15	2.481/1	F.V percjelles PV-500 Ø 2.5 mm2	ml	60		
16	2.481/2	F.V Çelesa e priza 10 A	cope	2		
17	2.483	F.V kuader ndrçimi	cope	1		
18	2.49	F.V priza bivalente 220V 10A 2P-T Vimar	cope	3		
19	2.485/a	Shuma B				
		Shuma A+B				
		T.V.Sh				
		SHUMA TOTALE				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e znj.Fatbardha Memaj ne fshatin Bilce , Njesia Administrative Velabisht

Nr.	Nr.analize	Pershkrimi I punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje suvatimi	m2	100		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	10		
		Shuma A				
		Punime ndertimore				
1	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m (antisizmik	m3	0.2		
2	2.109/2	Themel e xokol betoni C - 12/15	m3	1		
3	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.2		
4	2.262/3	Shtrese betoni C 12/15	m3	0.5		
5	2.70/2	Mur me tulle te lehtesuara dopio deri 3m me llaç perzier M25 t=20 cm	m3	3.2		
6	2.312	Suva brenda mur guri h=4m me krah, llaç perzier M 25	m2	70		
7	2.295	Tavan rrjete teli + suva	m2	42		
8	2.375	Dritare d/alumini tek xham.	m2	4.5		
9	2.383/2	F V dyer druri importi cilesi e II-te.	m2	3.2		
10	2.267/a	Shtrese me pllaka grez porcelanato	m2	40		
11	2.324/b	Plintuse grez importi, h = 10 cm	ml	32		
12	2.218	Çati vendi zakonshme HD-8m, mbuluar me tjegulla vendi	m2	74		
13	2.182	Konstruksione metalike te thjeshta+llamarine xingato per strehen	ton	0.4		
14	2.404	Boje hidroplastike	m2	50		
15	2.504	F.V WC alla turka importi	cope	1		
16	2.506	F.V bide importi porcelani	cope	1		
17	2.491/a	F.V tuba rakorderi ujesjellesi	ml	5		
		Shuma B				
		Shuma A+B				
		T.V.Sh				
		SHUMA TOTALE				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Syrja Kaceli ne fshatin Veleshnje Njesia Administrative Velabisht

Nr.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje suvatimi	m2	100		
		Shuma A				
		Punime ndertimore				
1	2.119/1a	Struktura b/a monolite C - 20/25, h ~ 4 m (brez b/a)	m3	4		
2	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.13		
3	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.2		
4	2.312	Suva brenda mur guri h~4m me krah, llaç perzier M 25	m2	60		
5	2.375	Dritare d/alumini tek xham.	m2	3.2		
6	2.383/2	F V dyer druri importi cilesi e II-te.	m2	5.24		
7	2.295	Tavan rrjete teli + suva	m2	40.5		
7	2.267/a	Shtrese me pllaka grez porcelanato	m2	40		
8	2.324/b	Plintuse grez importi, h = 10 cm	ml	36		
9	2.404	Boje hidroplastike	m2	60		
10	2.195	Hidroizolim me emulsion dhe dy duar bitumi dysHEMEJE	m2	22		
12	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	78.6		
13	480/3	F.V tub plastmasi Ø 22-26mm	ml	30		
14	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	20		
15	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	20		
16	2.483	F.V Çelesa e priza 10 A	cope	2		
17	2.49	F.V kuader ndriçimi	cope	1		
18	2.485/a	F.V priza bivalente 220V 10A 2P-T Vimar	cope	3		
		Shuma B				
		Shuma A+B				
		T.V.Sh				
		SHUMA TOTALE				999,730.22

Punoi
Ing.Rolinda Vellu





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Abastol Kuci ne fshatin Veleshnje , Njesia Administrative Velabisht

Nr.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m3	1		
2	An	Prishje suvatimi	m2	150		
3	An	Prishje mur guri	m3	1		
		Shuma A				
		Punime ndertimore				
1	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m (antisizmik	m3	2.15		
3	2.119/1a	Brez b/a e arkitrare b/a C20/25 h ~ 4m	m3	5		
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.15		
5	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.25		
6	2.312	Suva brenda mur gun h~4m me krah, llaç perzier M 25	m2	70		
7	2.295	Tavan rrjete teli + suva	m2	50		
8	2.375	Dritare d/alumini tek xham.	m2	3.5		
9	2.383/2	F V dyer druri importi cilesi e II-te.	m2	4		
10	2.267/a	Shtrese me pllaka grez porcelanato	m2	50		
11	2.324/b	Plintuse grez importi, h = 10 cm	ml	30		
12	2.219	Çati vendi zakonshme HD~8m, mbuluar, tjegulla marseleze	m2	125		
13	480/3	F.V tub plastmasi Ø 22-26mm	ml	20		
14	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	25		
15	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	28		
16	2.483	F.V Çelesa e priza 10 A	cope	2		
17	2.49	F.V kuader ndrçimi	cope	1		
18	2.485/a	F.V priza bivalente 220V 10A 2P-T Vimar		3		
		Shuma B				
		Shuma A+B				
		T.V.Sh				1,144,753.72
		SHUMA TOTALE				

Punoi
Ing.Rolinda Veliu



10

Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Duhanas Njesia Administrative Velabisht

Perfituesi : Osman Çalaj

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	An	Mur guri ne lartesi me llac te perziere M15	m3	5		
2	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	97		
3	2.295	Tavan rrjet teli + suva	m2	50		
4	2.31	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	90		
5	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	52		
6	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	5		
7	3.375	Dritare d/alumini tek xham.	m2	3		
					Shuma	
					Tvsh 20%	
					Totale	

Punoi
Ing.Meleqe Spahiu



MIRATOI
KRYETARI I BASHKISE
Ervin DEMO






PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Enver Guce ne fshatin Veleshnje, Njesia Administrative Velabisht

Nr.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje suvatimi	m2	80		
		Shuma A				
		Punime ndertimore				
1	2.119/1a	Struktura b/a monolite C - 20/25, h - 4 m brez b/a	m3	5		
2	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.15		
3	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.2		
4	2.312	Suva brenda mur guri h~4m me krah, llaç perzier M 25	m2	80		
5	2.375	Dritare d/alumini tek xham.	m2	7.5		
6	2.383/2	F V dyer druri importi cilesi e II-te.	m2	5		
7	2.295	Tavan rrjete teli + suva	m2	28		
8	2.267/a	Shtrese me pllaka grez porcelanato	m2	40		
9	2.324/b	Plintuse grez importi, h = 10 cm	ml	48		
10	2.279	Shtrese derrasa FM 2.5cm	m2	15		
11	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	105		
12	480/3	F.V tub plastmasi Ø 22-26mm	ml	20		
13	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	30		
14	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	40		
15	2.483	F.V Çelesa e priza 10 A	cope	2		
16	2.49	F.V kuader ndriçimi	cope	1		
17	2.485/a	F.V priza bivalente 220V 10A 2P-T Vimar	cope	3		
		Shuma B				
		Shuma A+B				
		T.V.Sh				
		SHUMA TOTALE				

Punoi
Ing.Rolinda Veliu



12.



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesa e z.Astrit Topi ne fshatin Velerik , Njesia Administrative Velabisht

Nr.rendi	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
		Punime nderimore				
1	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m (perforcim murat)	m3	1.3		
2	2.119/1a	Trare e arkitare b/a C20/25 h ~ 4m	m3	1.7		
3	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.62		
4	2.167	F V hekur betoni periodik Ø > 10 mm	ton	1.1		
5	2.64/2	Mure me tulle te plota me lartesi deri 3 m me llac perzier M 25	m3	15		
6	2.218	Çati vendi zakonshme HD-8m, mbuluar me tjegulla vendi	m2	77		
		Shuma				
		T.V.Sh				
		Shuma totale				

Punoj
Ing.Valentina Karabina

MIRATOJ
KRYETARI I BASHKISE
ERVIN DEMO



13



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Bashkim Zela ne fshatin Starove ,Njesia Administrative Velabisht

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
Punime prishje						
1	An	Prishje suvatimi	m2	70		
2	An	Prishje e shtresave ekzistuese dyshemeja	m2	70		
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	11		
Shuma A						
Punime ndertimore						
1	2.31	25	m2	150		
2	2.3	Suva solete h=4m me krah, llaç perzier M 25	m2	48		
3	2.262/3	Shtrese betoni C12/15 (dyshmeja)	m3	6.5		
4	2.386/2	Dyer te blinduara importi	m2	5.94		
5	3.375	Dritare d/alumini tek xham.	m2	3.2		
6	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	50		
7	2.332	Suva e zakonshme fasade mur guri h=8	m2	95		
8	2.404	Boje hidroplastike	m2	120		
Shuma B						
Punime elektrike						
1	2.481/1	F.V. Percjelles 1.5 mm	ml	130		
2	2.481/2	F.V. Percjelles 2.5 mm	"	150		
3	2.480/3	F.V. Tuba plasmasi flek. Ø 26	"	280		
4	2.483	F.V. Çelesa 10 A	cope	7		
5	2.485	F.V. Priza 10 A me tokezim	cope	12		
6	2.487	F.v kuti devijacioni plastike	cope	2		
7	2.486	F.V Portollampa normale 10 A	cope	7		
8	2. a-120	Llampe sinjalizimi 220V;1.2w	cope	6		
9	2.490/d	F.V. Kuader (60 x 80 x 20) cm	cope	1		
Shuma C						
Shuma A+B+C						
T.V.Sh						
Shuma totale						

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



19



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Ajlet Kondi ne fshatin Starove , Njësia Administrative Velabisht

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njësia	Sasia	Cmimi	Vlera
A		Punime prishje				
1	An	Prishje suvatimi	m2	35		
2	An	Prishje mur guri	m3	2.3		1
3	2.37/5b	Transport materiale nderfimi, dheu me auto deri 10.0 km	m3	10		
		Shuma A				
		Punime ndertimore				
1	2.54/2	Mur guri ne lartesi (50 cm shtese)	m3	6.8		7
2	2.117/1	Kollona b/a monolite C - 16/20, h - 4 m (perforcim murat)	m3	7.8		15
3	2.119/1a	Trare e arkitraro b/a C20/25 h ~ 4m	m3	6.8		14
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.34		11
5	2.167	F V hekur betoni periodik Ø >10 mm	ton	0.45		10
6	2.312	Suva brenda mur guri h~4m me krah, llaç perzier M 25	m2	65		
5	2.295	Tavan rrjete vell + suva	m2	40		
8	3.375	Dritare d/alumini tek xham.	m2	3.8		
9	2.383/2	F V d'yer dnuri importi ciliasi e li-te.	m2	4.4		1
10	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	53		
11	2.404	Boje hidroplastike	m2	80		
12	2.219	Çati vendi zakonshme HD~8m, mbuluar me tjegullia vendi	m2	73		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

MIRATO
KRYETARI I BASHKISE
ERVIN DEMO

Punoi
Ing.Valentina Karabina

16



PREVENTIV PUNIMESH

Objekt: Punime riparimi e mirembajtje ne banesen e z.Kadri Shane ne fshatin Gjoroven , Njesia Administrative Velabisht

Nr.rend.	Nr.analize	Pershkrimi I punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
1	An	Prishje mur guri	m3	2		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	10		
3	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m3	2		
		Shuma A				
		Punime ndertimore				
1	2.119/1a	Brez b/a e arkitrare b/a C20/25 h ~ 4m	m3	7		
2	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m (antisizm)	m3	4.5		
3	2.54/2	Mur guri ne lartesi	m3	3		
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.6		
5	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.5		
6	3.375	Dritare d/alumini tek xham.	m2	3.1		
7	2.383/2	F V dyer druri importi cilesi e II-te.	m2	2.8		
8	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	96		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoj
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE

ERVIN DEMO





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Kadri Gremshi ne fshatin Gjoroven , Njesia Administrative Velabisht

Nr.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje suvatimi	m2	70		
		Shuma A				
		Punime ndertimore				
1	2.119/1a	Brez b/a e arkitrare b/a C20/25 h ~ 4m	m3	4.5		
2	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.15		
3	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.2		
4	2.312	Suva brenda mur guri h~4m me krah, llaç perzier M 25	m2	60		
5	2.295	Tavan rrjete teli + suva hidroizolim me emulsion dhe dy duar bitumi dysHEMEJE /mur guri anesor ne aksin B	m2	40		
6	2.195	Dritare d/alumini tek xham.	m2	27		
7	2.375	F V dyer druri importi cilesi e II-te.	m2	4.9		
9	2.267/a	Shtrese me plaka grez porcelanato	m2	30		
10	2.324/b	Plintuse grez importi, h = 10 cm	ml	35		
11	2.218	Çati vëndi zakonshme HD~8m, mbluar me tjegulla vëndi	m2	90		
		Shuma B				
		Shuma A+B				
		T.V.Sh				
		SHUMA TOTALE				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO

17



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e znj.Selime NazeraJ ne fshatin Duhanas , Njesia Administrative Velabisht

Nr.re nd.	Nr.anal ize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m3	3.2		
2	An	Prishje suvatimi	m2	70		
3	An	Prishje mur guri	m3	3		
4	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	3		
		Shuma A				
		Punime ndertimore				
1	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m (perforcim murat	m3	4.8		
2	2.54/2	Mur guri ne lartesi (50cm shtese)	m3	4.2		
3	2.119/1a	Trare e arkitrare b/a C20/25 h ~ 4m	m3	2.8		
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.45		
5	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.35		
6	2.312	Suva brenda mur guri h~4m me krah, llaç perzier M 25	m2	40		
7	2.295	Tavan rrjete teii + suva	m2	32	18	
8	3.375	Dritare d/alumini tek xham.	m2	2.3		
9	2.383/2	F V dyer druri importi cilesi e II-te.	m2	2.8		
10	2.267/a	Shtrese me pilaka grez porcelanato	m2	28		
11	2.324/b	Plintuse grez importi, h = 10 cm	ml	24		
12	2.195	Hidroizolim me emulsion dhe dy duar bitumi dysHEMEJE	m2	20		
13	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	73		
14	480/3	F.V tub plastmasi Ø 22-26mm	ml	40		
15	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	38		
16	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	34		
17	2.483	F.V Çelesa e priza 10 A	cope	2		
18	2.49	F.V kuader ndrçimi	cope	1		
19	2.485/a	F.V priza bivalente 220V 10A 2P-T Vimar	cope	3		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



18



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Xhovan Guga ne lagjen "10 Korriku", Njesia Administrative Nr.2, Berat

Nr.rend	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
1	2.426/2	Prishje mur bloku	m3	0.5		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	2		
		Shuma A				
		Punime ndertimore				
1	2.119/1a	Struktura b/a monolite C - 20/25, h ~ 4 m	m3	8		
2	2.64/2	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 25	m3	5		
3	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.6		
4	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.6		
5	3.375	Dritare d/alumini tek xham.	m2	3		
6	2.383/2	F V dyer druri importi cilesi e II-te.	m2	2.2		
7	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	50		
8	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	5		
9	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	9.2		
10	480/3	F.V tub plastmasi Ø 22-26mm	ml	60		
11	2.481/1	F.V perçjelles PV-500 Ø 1.5 mm ²	ml	48		
12	2.481/2	F.V perçjelles PV-500 Ø 2.5 mm ²	ml	51		
13	2.483	F.V Çelesa e priza 10 A	cope	4		
14	2.490	F.V kuader ndriçimi	cope	1		
15	2.485/a	F.V priza bivalente 220V 10A 2P-T Vimar	cope	3		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO

19



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Sulo Gorani ne lagjen "30 Vjetori", Njesia Administrative Nr.2, Berat

Nr.rend	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
1	An	Prishje suvatimi	m2	100		
2	2.426/2	Prishje mur bloku	m3	3		
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	4		
		Shuma A				
		Punime ndertimore				
5	2.119/1a	Struktura b/a monolite C - 20/25, h ~ 4 m	m3	8.5		
6	2.64/2	Mur me tulle plotu ne lartesi deri 3m me llaç perzier M 25	m3	6		
7	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.55	1	
8	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.76	1	
9	3.375	Dritare d/alumini tek xham.	m2	4		
10	2.383/2	F V dyer druri importi cilesi e II-te.	m2	7.94		
11	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama/taraca	m2	60		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e znj.Nevreze Veziraj ne lagjen "30 Vjetori" , Njesia Administrative Nr.2, Berat

Nr.rend	Nr.analize	Pershkrimi I punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
1	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	2		
		Shuma A				
		Punime ndertimore				
1	2.310	Suva brenda murature me krah, llaç perzier M 25	m2	85		
2	2.295	Tavan rrjete teli + suva	m2	32		
3	2.195	Hidroizolim me emulsion dhe dy duar bitumi dyshemeje	m2	32		
4	2.267/a	Shtrese me pllaka grez porcelanato	m2	32		
5	2.324/b	Plintuse grez importi, h = 10 cm	ml	31.54		
6	2.273	Shtrese pllaka mermeri t=2cm	m2	1		
7	3.375	Dritare d/alumini tek xham.	m2	1.2		
8	2.383/2	F V dyer druri importi cilesi e II-te.	m2	3.6		
9	2.404	Boje hidroplastike	m2	120		
10	2.334	Suva e zakonshme fasade mur tulle lartesi mbi 8 m	m2	100		
11	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	47		
12	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	6		
13	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	9.12		
14	480/3	F.V tub plastmasi Ø 22-26mm	ml	60		
15	2.481/1	F.V percjelles PV-500 Ø 1.5 mm2	ml	48		
16	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	51		
17	2.483	F.V Çelesa e priza 10 A	cope	4		
18	2.490	F.V kuader ndriçimi	cope	1		
19	2.485/a	F.V priza bivalente 220V 10A 2P-T Vimar	cope	3		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



21



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Calli Zerelari ne lagjen "30 Vjetori" , Njesia Administrative Nr.2

Nr.rend	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje suvatimi tavane	m2	174		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	2		
		Shuma A				
		Punime ndertimore				
1	2.310	Suva brenda murature me krah, llaç perzier M 25	m2	60		
2	2.300	Suva solete h ~ 4 m me drejtues, me krah	m2	174		
3	2.267/a	Shtrese me pllaka grez porcelanato	m2	103		
4	2.324/b	Plintuse grez importi, h = 10 cm	ml	120		
5	3.375	Dritare d/alumini tek xham.	m2	4.1		
6	2.383/2	F V dyer druri importi cilesi e II-te.	m2	3.52		
7	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama/taraca	m2	174.2		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO

22



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Kujtim Pepaj ne katin e dyte te ndertesës , Lagjja "10- Korriku ",
NJIA nr.2 Berat

Nr.rend.	Nr.analize	Pershkrimi I punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje te catise ekzistuese	m2	60		
2	2.431	Skele metalike me tubo fasade > 12m	m2	200		
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	8		
		Shuma A				
	B	Punime ndertimore				
1	2.295	Tavan rrjete teli + suva	m2	50		
2	3.375	Dritare d/alumini tek xham.	m2	6		
3	2.383/2	F V dyer druri importi cilesi e II-te.	m2	6.3		
4	2.267/a	Shtrese me pllaka grez porcelanato	m2	40		
5	2.324/b	Plintuse grez importi, h = 10 cm	ml	30		
6	2.273	Shtrese pllaka mermeri t=2cm	m2	1		
7	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	42		
8	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	60		
9	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	40		
10	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	30		
		Shuma B				
		Ahuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO

23



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Saimir Muhameti ne lagjen "30 Vjetori", Njesia Administrative Nr.2, Berat

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
1	An	Prishje shtresash ekzistuese	m2	100		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	1		
		Shuma A				
		Punime ndertimore				
1	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama/taraca	m2	120		
2	2.300	Suva solete h ~ 4 m me drejtues, me krah	m2	100		
3	2.404	Boje hidroplastike	m2	100		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO

24

Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Kostren i vogel Njesia Administrative Roshnik

Perfituesi : Alije Zylali

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	2.117/1a	Kollona b/a monolite C 20/25 h ~ 4m	m3	0.9		
2	2.119/1	Trare e arkitrare b/a C - 16/20, h ~ 4 m	m3	3		
3	2.166	FV hekur betoni periodik Ø6-10 mm	ton	0.17		
4	2.167	FV hekur betoni periodik Ø >10 mm	ton	0.27		
5	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	79		
6	2.295	Tavan rrjet teli + suva	m2	53.3		
7	2. 310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	125		
8	2.331	Suva e zakonshme fasade	m2	40		
9	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	54		
10	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	6.3		
11	3.375	Dritare d/alumini tek xham.	m2	3.2		
12	2.404	Boje hidroplastike	m2	278		
13	480/3	F v Tub plasmasi Ø 22-26 mm	ml	70		
14	2.481/1	F v percjelles Ø 1.5 mm	ml	150		
15	2.481/2	F v percjelles Ø 2.5 mm	ml	150		
16	2.481/3	F v percjelles Ø 4 mm	ml	50		
17	2.481/4	F v percjelles Ø 6 mm	ml	13		

Punoi
Ing.Meleqe Spahiu

MIRATOI
KRYETARI I BASHKISE
Ervin DEMO



Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Kostren i vogel Njesia Administrative Roshnik

Perfituesi : Shyqyri Kuqi

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	103		
2	2.295	Tavan rrjet teli + suva	m2	65		
3	2.31	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	180		
4	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	65		
5	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	7.2		
6	3.375	Dritare d/alumini tek xham.	m2	5.5		
						T

Punoi
Ing.Meleqe Spahiu



MIRATOI
KRYETARI I BASHKISE
Ervin DEMO



Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Bogdan I poshtem Njesia Administrative Roshnik

Perfituesi : Nazmi Kotollaku

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
		A.Punime Ndertimi				
1	An	Prishje çatie	m2	57		
2	2.54/1	Mur guri ne lartesi me llac te perziere M15	m3	23		
3	2.121/1	Brez b/a C 16/20, h ~ 8 m	m3	1		
4	2.166	FV hekur betoni periodik ø6-10mm	ton	0.5		
5	2.167	FV hekur betoni periodik ø>10mm	ton	0.3		
6	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	57		
7	2.295	Tavan rrjet teli + suva	m2	32		
8	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	89.6		
9	2.331	Suva e zakonshme fasade	m2	84		
10	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	35		
11	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	3.6		
12	3.375	Dritare d/alumini tek xham.	m2	2.6		
13	2.404	Boje hidroplastike	m2	174		
14	480/3	F v Tub plasmasi Ø 22-26 mm	ml	80		
15	2.481/1	F v percjelles Ø 1.5 mm	ml	160		
16	2.481/2	F v percjelles Ø 2.5 mm	ml	140		
17	2.481/3	F v percjelles Ø 4 mm	ml	70		
18	2.481/4	F v percjelles Ø 6 mm	ml	15		
19	2.485	F.V Çelesa e priza 10 A me nulifikim	cope	5		
20	2.490/1	F v automat elektromagnetik 2P 240 V 32A	cope	1		
						T
						T

Punoi
Ing.Melege Spahiu

MIRATOI
KRYETARI I BASHKISE
Ervin DEMO



27

Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Mimias Njesia Administrative Roshnik

Perfituesi : Blerti Doraci

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
		A.Punime Ndertimi				
1	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	103		
2	2.295	Tavan rrjet teli + suva	m2	55		
3	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	120		
4	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	55		
5	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	7		
6	3.375	Dritare d/alumini tek xham.	m2	5.3		
7	2.404	Boje hidroplastike	m2	224		
8	480/3	F v Tub plasmasi Ø 22-26 mm	ml	80		
9	2.481/1	F v percjelles Ø 1.5 mm	ml	160		
10	2.481/2	F v percjelles Ø 2.5 mm	ml	140		
11	2.481/3	F v percjelles Ø 4 mm	ml	70		
12	2.481/4	F v percjelles Ø 6 mm	ml	15		
13	2.485	F.V Çelesa e priza 10 A me nulifikim	cope	6		
14	2.490/1	F v automat elektromagnetik 2P 240 V 32A	cope	1		

Punoi
Ing.Meleqe Spahiu

MIRATOI
KRYETARI I BASHKISE
Ervin DEMO

Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati kostren Njesia Administrative Roshnik

Perfituesi :Neki Hoxha

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	2.5	Germim e mbushje dheu me krah kategoria III per themele h=1.5m	m3	31		
2	2.52/1	Mur guri themel e xokol me llac te perzier M 15	m3	25.2		
3	An	Mur guri lartesi deri me llac te perzier M-15	m3	35		
4	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	69		
5	2.295	Tavan rrjet teli + suva	m2	38		
6	2.310	Suva brenda mur tulle h=4m me krah, llaç perzier M 25	m2	96		
7	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	40		
8	2.404	Boje hidroplastike	m2	100		
9	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	5.1		
10	3.375	Dritare d/alumini tek xham.	m2	2.4		
11	2.481/1	F v percejelles Ø 1.5 mm	ml	120		
12	2.481/2	F v percejelles Ø 2.5 mm	ml	100		
13	2.481/3	F v percejelles Ø 4 mm	ml	70		
14	2.481/4	F v percejelles Ø 6 mm	ml	15		
15	2.485	F.V Çelesa e priza 10 A me nulifikim	cope	3		
						T
						T

Punoi
Ing.Meleqe Spahiu



MIRATOI
KRYETARI I BASHKISE
Ervin DEMO




Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Mbreshtan Njesia Administrative Sinje

Perfituesi : Dudi Shtrepi

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	84		
2	2.295	Tavan rrjet teli + suva	m2	31		
3	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	98		
4	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	33		
5	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	4.9		
6	3.375	Dritare d/alumini tek xham.	m2	2.5		
						T

Punoi
Ing.Meleqe Spahiu



MIRATOI
KRYETARI I BASHKISE
Ervin DEMO



Preventiv Punimesh**Objekti :** Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje**Projektuesi :** Bashkia Berat**Vendodhja :** Fshati Mbjesheve Njesia Administrative Sinje**Perfituesi :** Agim Sinani

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	An	Mur guri ne lartesi me llac te perziere M15	m3	7		
2	2.117/1a	Kollona b/a monolite C 20/25 h ~ 4m	m3	0.4		
3	2.121/1	Brez b/a C 16/20, h ~ 8 m	m3	0.78		
4	2.119/1	Arkitrare b/a C16/20 h-4 m	m3	0.13		
5	2.166	FV hekur betoni periodik ø6-10mm	ton	0.14		
6	2.167	FV hekur betoni periodik ø>10mm	ton	0.28		
7	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	70		
8	2.295	Tavan rrjet teli + suva	m2	49		
9	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	155		
10	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	40		
11	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	6.5		
12	3.375	Dritare d/alumini tek xham.	m2	3.6		
						T

Punoi
Ing.Meleqe Spahiu



MIRATOI
KRYETARI I BASHKISE
Ervin DEMO




Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Mbjeshove Njesia Administrative Sinje

Perfituesi : Nuri Velçanaku

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
		A.Punime Ndertimi				
2	An	Mur guri ne lartesi me llac te perziere M15	m3	16		
3	2.117/1a	Kollona b/a monolite C 20/25 h ~ 4m	m3	0.6		
4	2.121/1	Brez b/a C 16/20, h ~ 8 m	m3	0.96		
5	2.119/1	Arkitrare b/a C16/20 h-4 m	m3	0.13		
6	2.166	FV hekur betoni periodik ø6-10mm	ton	0.16		
7	2.167	FV hekur betoni periodik ø>10mm	ton	0.31		
8	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	54		
9	2.295	Tavan rrjet teli + suva	m2	33		
10	2.310	Suva brenda mur tulle h~4m me krahe, llac perzier M 25	m2	91		
11	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	34		
12	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	3.8		
13	3.375	Dritare d/alumini tek xham.	m2	3		
14	2.331	Suva e zakonshme fasade	m2	84		
15	2.404	Boje hidroplastike	m2	175		
16	480/3	F v Tub plasmasi Ø 22-26 mm	ml	80		
17	2.481/1	F v percjelles Ø 1.5 mm	ml	160		
18	2.481/2	F v percjelles Ø 2.5 mm	ml	150		
19	2.481/3	F v percjelles Ø 4 mm	ml	80		
20	2.481/4	F v percjelles Ø 6 mm	ml	20		
21	2.485	F.V Çelesa e priza 10 A me nulifikim	cope	6		
22	2.490/1	F v automat elektromagnetik 2P 240 V 32A	cope	1		

Punoi
Ing.Meleqe Spahiu

MIRATOI
KRYETARI I BASHKISE
Ervin DEMO

36

Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Osmenzeze Njesia Administrative Sinje

Perfituesi : Jemin Hameti

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	2.54/1	Mur guri ne lartesi me llac te perziere M15	m3	8		
2	2.117/1a	Kollona b/a monolite C 20/25 h ~ 4m	m3	0.4		
3	2.121/1	Brez b/a C 16/20, h ~ 8 m	m3	0.78		
4	2.119/1	Arkitrare b/a C16/20 h-4 m	m3	0.13		
5	2.166	FV hekur betoni periodik ø6-10mm	ton	0.14		
6	2.167	FV hekur betoni periodik ø>10mm	ton	0.28		
7	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	70		
8	2.295	Tavan rrjet teli + suva	m2	48		
9	2.310	Suva brenda mur tulle h~4m me krah, llac perzier M 25	m2	176		
10	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	52		
11	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	5.94		
12	3.375	Dritare d/alumini tek xham.	m2	5.4		
13	2.404	Boje hidroplastike	m2	221		
14	480/3	F v Tub plasmasi Ø 22-26 mm	ml	100		
15	2.481/1	F v percjelles Ø 1.5 mm	ml	170		
16	2.481/2	F v percjelles Ø 2.5 mm	ml	150		
17	2.481/3	F v percjelles Ø 4 mm	ml	90		
18	2.481/4	F v percjelles Ø 6 mm	ml	20		
19	2.485	F.V Çelesa e priza 10 A me nulifikim	cope	5		
20	2.490/1	F v automat elektromagnetik 2P 240 V 32A	cope	1		
						1

Punoi
Ing.Meleqe Spahiu

MIRATOI
KRYETARI I BASHKISE
Ervin DEMO

Preventiv Punimesh**Objekti :** Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje**Projektuesi :** Bashkia Berat**Vendodhja :** Fshati Mbreshtan Njesia Administrative Sinje**Perfituesi :** Merushe Muhameti

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	2.5	Germim e mbushje dheu me krah kategoria III per themele h=1.5m	m3	31		
2	2.52/1	Mur guri themel e xokol me llac te perzier M 15	m3	25.2		
3	An	Mur guri lartesi deri me llac te perzier M-15	m3	35		
4	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	41		
5	2.295	Tavan rrjet teli + suva	m2	28		
6	2.31	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m2	92		
7	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	31		
8	2.404	Boje hidroplastike	m2	92		
9	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	5.1		
10	3.375	Dritare d/alumini tek xham.	m2	2.4		
11	2.481/1	F v percjelles Ø 1.5 mm	ml	120		
12	2.481/2	F v percjelles Ø 2.5 mm	ml	100		
13	2.481/3	F v percjelles Ø 4 mm	ml	70		
14	2.481/4	F v percjelles Ø 6 mm	ml	15		
15	2.485	F.V Çelesa e priza 10 A me nulifikim	cope	3		
						T

Punoj
Ing.Meleqe Spahiu



MIRATOI
KRYETARI I BASHKISE
Ervin DEMO



08



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Yzeir Mehmetaj ne fshatin Osmenzez, Njesia Administrative Sinje

Nr.re nd.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
Punime prishje e germimi						
1	An	Prishje mur guri	m3	6		
2	2.1	Germim dheu me krah e transport me k dore 10 m, kategoria III	m3	3		
Shuma A						
Punime ndertimore						
1	2.52/2	Mur guri themel e kokol me llaç perzier M 25	m3	12.2		
2	2.54/2	Mur guri ne lartesi deri 3m me llaç çimento M 25	m3	11.5		
3	2.121/1	Brez b/a C 16/20, h ~ 8 m (antisizmik)	m3	2.1		
4	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m (antisizmike)	m3	3.2		
5	2.119/1a	Struktura b/a monolite C - 20/25, h ~ 4 m	m3	4.5		
6	2.64/2	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 25	m3	1.8		
7	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.4		
8	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.48		
9	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	90		
Shuma B						
shuma A+B						
T.V.Sh						
Shuma totale						

Punci
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



Preventiv Punimesh

Objekti : Tip per Rehabilitim/Perforcim banesash ekzistuese qe jane ne rrezik shembje

Projektuesi : Bashkia Berat

Vendodhja : Fshati Molisht Njesia Administrative Sinje

Perfituesi : Qerime Bendo

Nr	Nr analize	Emertimi I punimeve	Njesia	Sasia	Cmimi	Vlera
A.Punime Ndertimi						
1	2.54/1	Mur guri ne lartesi me llac te perziere M15	m3	22		
2	2.218	Cati vendi HD-8m,mbuluar me tjegulla vendi	m2	24		
3	2.295	Tavan rrjet teli + suva	m2	11.74		
4	2.31	Suva brenda mur tulle h~4m me krah, llac perzier M 25	m2	39		
5	2.334	Suvatim I jashtem I zakonshem	m2	49.8		
6	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	12.28		
7	2.388/1	FV dyer te brendeshme tamburate te rimesuara	m2	1.98		
8	3.375	Dritare d/alumini tek xham.	m2	1.2		
9	2.404	Boje hidroplastike	m2	103		
10	480/3	F v Tub plasmasi Ø 22-26 mm	ml	20		
11	2.481/1	F v percjelles Ø 1.5 mm	ml	50		
12	2.481/2	F v percjelles Ø 2.5 mm	ml	50		
13	2.481/3	F v percjelles Ø 4 mm	ml	20		
14	2.481/4	F v percjelles Ø 6 mm	ml	10		
15	2.485	F.V Çelesa e priza 10 A me nulifikim	cope	3		
16	2.490/1	F v automat elektromagnetik 2P 240 V 32A	cope	1		
					S	
					Tv	
					Tot	

Punoi
Ing.Meleqe Spahiu



MIRATOI
KRYETARI I BASHKISE
Ervin DEMO





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Rexhep Mollaj ne lagjen Clirim,Rajoni nr 1

Nr.rend.	Nr.analize	Pershkrimi I punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje suvatimi	m2	70		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	11		
		Shuma A				
		Punime ndertimore				
1	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m2	55		
2	2.300	Suva solete h ~ 4 m me drejtues, me krah	m2	55		
3	2.262/4	Shtrese betoni C16/20	m3	7		
4	2.264	Shtrese lluster cemento 1:2	m2	42		
5	2.195	Hidroizolim me emulsion dhe dy duar bitumi dysHEMEJA	m2	50		
6	2.312	Suva brenda mur guri h=4m me krah, llaç perzier M 25	m2	100		
7	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	36		
8	2.326	Veshje me pllaka majolike	m2	7		
9	2.324/b	Plintuse grez importi, h = 10 cm	ml	41		
10	2.308/a	Suvatim me grafiato h>4m	m2	35		
11	2.332	Suva e zakonshme fasade mur guri h=8	m2	92		
12	2.404	Boje hidroplastike	m2	110		
13	2.383/2	F V dyer druri importi cilesi e II-te.	m2	5.28		
14	2.386/2	Dyer te blinduara importi	m2	1.98		
15	3.375	Dritare d/alumini tek xham.	m2	3.2		
		Shuma B				
		Punime elektrike				
1	2.481/1	F.V. Percjelles 1.5 mm	ml	130		
2	2.481/2	F.V. Percjelles 2.5 mm	"	150		
3	2.480/3	F.V. Tuba plasmasi flek. Ø 26	"	280		
4	2.483	F.V. Çelesa 10 A	cope	7		
5	2.485	F.V. Priza 10 A me tokezim	cope	12		
6	2.487	F.v kuti devijacioni plastike	cope	2		
7	2.486	F.V Portollampa normale 10 A	cope	7		
8	2. a-120	Llampe sinjalizimi 220V;1.2w	cope	6		
11	2.490/d	F.V. Kuader (60 x 80 x 20) cm	cope	1		
		Shuma C				
		Punime hidrosanitare				
1	2.515	F.V pilete dysHEMEJA Ø50 mm	cope	1		
2	2.501	F.V WC allafrenga importi	cope	1		
3	2.495	F.V lavaman porcelani importi me mishelator	cope	1		
4	An-9	F.V Saracineska PPR 1/2 "	cope	2		



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z. Artan Dropulli ,Rajoni nr 1

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime ndertimore				
1	2.218	Çati vendi zakonshme HD-8m, mbuluar me tregulla vendi	m2	95		
2	2.121/1	Brez b/a C16/20 ,h- 8m	m3	0.7		
	2.166	F.V hekur betoni periodik Ø 6 - 10 mm	ton	0.34		
3	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	11.2		
4	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	29		
		Shuma A				
		T.V.SH				
		Shuma totale				

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e znj.Nabile Agalliu ,Rajoni nr 1

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje te catise ekzistuese	m2	80		
2	2.431	Skele metalike me tubo fasade > 12m	m2	830		
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	70		
		Shuma A				
		Punime ndertimore				
1	2.218	Cati vendi zakonshme HD-8m, mbuluar me ljegulla vendi	m2	80		
2	2.297/a	Tavan me kartonshes	m2	65		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



43



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e znj. Lutfije Suku ne lagjen "Clirim" , Njesia Administrative Nr.1

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Heqja e shtresave ekzistuese te dyshemese	m2	40		
2	An	Prishje suvatimi	m2	150		
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	3		
		Shuma A				
		Punime ndertimore				
1	3.207	Shtrese çakelli t=8cm, perhapur e ngjeshur me makineri	m3	3		
2	2.258	Nenshtrese zhavori	m3	2.5		
3	2.262/3	Shtrese betoni C 12/15	m3	2.5		
4	2.195	Hidroizolim me emulsion dhe dy duar bitumi dyshemeje	m2	200		
5	2.264	Shtrese lluster çimento 1:2	m2	40		
6	2.267/a	Shtrese me pllaka grez porcelanato	m2	75		
7	2.324/b	Plintuse grez importi, h = 10 cm	ml	71		
8	2.326	Veshje me pllake majolike	m2	17		
9	3.375	Dritare d/alumini tek xham.	m2	5.2		
10	2.383/2	F V dyer druri importi cilesi e II-te.	m2	4.2		
11	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25		180		
12	2.300	Suva solete h ~ 4 m me drejtues, me krah	m2	75		
13	2.404	Boje hidroplastike	m2	250		
14	2.273	Shtrese pllaka mermeri t=3cm	m2	1.6		
15	2.495	F.V lavaman porcelani importi me mishelator	cope	1		
16	2.504	F.V WC alla turka importi	cope	1		
17	2.506	F.V bide importi porcelani	cope	1		
18	2.491/a	F.V tuba rakorderi ujesjellesi	ml	15		
19	480/3	F.V tub plastmasi Ø 22-26mm	ml	80		
20	2.481/1	F.V percejelles PV-500 Ø 1.5 mm2	ml	75		
21	2.481/2	F.V percejelles PV-500 Ø 2.5 mm2	ml	80		
22	2.483	F.V Çelesa e priza 10 A	cope	10		
23	2.490	F.V kuader ndriçimi	cope	1		
24	2.485/a	F.V priza bivalente 220V 10A 2P-T Vimar	cope	8		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

REPUBLIKA E SHQËRIE
 QYTARËTARI
 KRYETARI I BASHKISE
 ERVIN DEMO
 BERAT

7 (44)



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Roland Brisku ne lagjen "Clirim" , Njesia Administrative Nr.1

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
1	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	3		
		Shuma A				
		Punime ndertimore				
1	2.310	Suva brenda murature me krah, llaç perzier M 25	m2	75		
2	2.295	Tavan rrjete telli + suva	m2	65		
3	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	40		
4	3.375	Dritare d/alumini tek xham.	m2	2.2		
5	2.324/b	Plintuse grez importi, h = 10 cm	ml	48		
6	2.218	Çati vendi zakonshme HD~8m, mbuluar me tjegulla vendi	m2	110		
7	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100 mm	ml	12		
8	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33 cm	ml	42		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Rolinda Veliu

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



45



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Adriatik Kanani ,Rajoni nr 3

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje e germimi				
		Germim dheu me krah e transport me k dore 10 m.				
1	2.1	kategoria III				
2	An	Prishje mur guri	m3	34		
		Shuma A	m2	84		
		Punime ndertimore				
1	2.52/2	Mur guri themel e xokol me llaç perzier M 25	m3	19		
2	2.54/2	Mur guri ne lartesi deri 3m	m3	21		
3	2.121/1	Brez b/a C 16/20, h ~ 8 m (antisizmik)	m3	1.6		
4	2.117/1	Kollona b/a monolite C - 16/20, h ~ 4 m (antisizmike)	m3	3.2		
5	2.117/1	Strukture monolite b/a monolite C - 16/20,	m3	9		
6	2.64/2	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 25	m3	3		
7	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	0.6		
8	2.167	F V hekur betoni periodik Ø > 10 mm	ton	0.7		
9	2.310	Suva brenda murature me krah, llaç perzier M 25	m2	70		
		Shuma B				
		shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoj
Ing.Valentina Karabina

MIRATOJ
KRYETARI I BASHKISE
ERVIN DEMO





PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e znj.Fitnete Kanani ,Rajoni nr 3

Nr.rend.	Nr.analize	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
A						
Punime prishje						
1	An	Prishje suvatimi	m2	70		
2	2.426	Prishje mur tulle pa pastrim	m3	0.5		
3	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	8		
Shuma A						
Punime ndertimore						
1	2.310	Suva brenda mur tulle h=4m me krah, llaç perzier M 25	m2	45		
2	2.300	Suva solete h = 4 m me drejtues, me krah	m2	65		
3	2.64/2	Mur me tulle plota ne lartesi deri 3m me llaç perzier M 25	m3	1.9		
4	2.86	Mur me tulle me 6 vrime, t=12cm, h=3m, llaç perzier M15	m3	2.1		
5	2.395	Dyer d/alumini tek xham,	m2	5.4		
6	2.386/2	Dyer te blinduara importi,	m2	2.1		
7	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	17.2		
8	2.324/b	Plintuse grez importi, h = 10 cm	m1	20		
9	2.326	Veshje me pllake majolike	m2	15		
10	2.404	Boje hidroplastike	m2	90		
11	2.195	Hidroizolim me emulsion dhe dy duar bitumi	m2	5		
12	2.273	Shtrese pllaka mermeri t=3cm	m2	1		
Shuma B						
Punime elektrike						
1	2.481/1	F.V. Percjelles 1,5 mm	m1	130		
2	2.481/2	F.V. Percjelles 2,5 mm	"	150		
3	2.480/3	F.V. Tuba plasmasi flek. Ø 26	"	280		
4	2.483	F.V. Çelesa 10 A	cope	7		
5	2.485	F.V. Priza 10 A me tokezim	cope	12		
6	2.487	F.v kuti devijacioni plastike	cope	2		
7	2.486	F.V Portollampa normale 10 A	cope	7		
8	2. a-120	Llampe sinjalizimi 220V;1.2w	cope	6		
11	2.490/d	F.V. Kuader (60 x 80 x 20) cm	cope	1		
Shuma C						
Shuma A+B+C						
T.V.Sh						
Shuma totale						

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO



46



PREVENTIV PUNIMESH

Objekt : Punime riparimi e mirembajtje ne banesen e z.Roland Kanani ,Rajoni nr 3

Nr.rend.	Nr.analize	Pershkrimi I punimeve	Njesia	Sasia	Cmimi	Vlera
	A	Punime prishje				
1	An	Prishje suvatimi	m2	70		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	11		
		Shuma A				
		Punime ndertimore				
1	2.312	Suva brenda mur guri h=4m me krah, llaç perzier M 25	m2	60		
2	2.295	Tavan rrjete teli + suva	m2	50		
3	2.383/2	Fv dyer druri importi cilesi e II- te	m2	6,5		
4	3.375	Dritare d/alumini tek xham.	m2	10		
5	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m2	47		
6	2.324/b	Plintuse grez importi ,h= 10 cm	ml	46		
7	2.195	Hidroizolim me emulsion dhe dy duar bitumi dyshemeje	m2	50		
8	2.218	Çati vendi zakonshme HD-8m, mbuluar me tjegulla vendi	m2	70		
		Shuma B				
		Shuma A+B				
		T.V.Sh				
		Shuma totale				

Punoi
Ing.Valentina Karabina

MIRATOI
KRYETARI I BASHKISE
ERVIN DEMO

