

**BASHKIA VAU DEJES**

Preventiv Punimesh

Objekti: Sistemim asfaltim rruges e brendshme Rranxa

Nr. Analize	Emertimi i punimeve	Njesia	Sasia	Cmimi	Vlera
A. Punime germimi dhe mbushje					
3.107/b	Germim dheu me ekskavator zingjir, 1.0 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne toke	m3	1260.9		
An.164/1 b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	60		
Shuma per punimet e germimit dhe mbushjes / Shuma A					
B. Punime shtresash rrugore					
3.211	Shtrese cakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	1779		
3.212/b	Shtrese stabilizant t=10cm	m2	8897		
3.212/a	Shtrese stabilizanti t=5cm	m2	937		
3.222/1	Shtrese binderi me granil gur kave,5cm,me makineri	m2	6556		
3.224/1	Shtrese asfaltobetoni me granil guri kave, 3cm, me makineri	m2	6556		
Shuma per punimet e shtresave / Shuma B					
C. Punime per sinjalistiken					
An151	Vizime me boje bikomponente (shirit 12cm ne 2 anet e rruges)	m ²	450		
3.243/1	Struktura te holla monolite betoni C 16/20 (per kuneten)	m ³	30		
An	Kanal betoni parafabrikat	ml	409		
An158	FV tabela te ndryshme rrugore D=60cm	cope	8		
Shuma per punimet e sinjalistikes / Shuma C					
Shuma per punimet e rruges (A-D)					
					Tvsh
Shuma totale me Tvsh					

Punoi:
"LENI-ING" sh.p.k
Ing. Nikoll Paluca