



NET - GROUP

NET-GROUP SH.P.K

ADRESA: TIRANË, RRUGA HAXHI DALLIU, HYRJA I, APARTAMENTI 0

SHERBIM PROJEKTIMI

**Objekti: "SISTEMIM ASFALTIM LAGJIA HOLTA, "ISH
KONSERVIMI", BASHKIA GRAMSH"**

PREVENTIV MEMEC

PROJEKT ZBATIM
TIRANE, 2022



PREVENTIV I PUNIMEVE



Objekti: SISTEMIM ASFALTIM LAGJIA HOLTA, "ISH KONSERVIMI", BASHKIA GRAMSH
Investitori: Bashkia Gramsh

Nr	Nr.An	Pershkrimi i punimeve	Njesia	Sasia	Cmimi	Vlera
PUNIME PRISHJE/SHPYLLEZIMI						
1	3.3	Prerje pemesh Ø10-20cm	cope	12		
2	2.426/5	Prishje muresh betoni	m ³	11		
3	2.426/3	Prishje shtresa betoni	m ³	30		
SHUMA I						
PUNIME DHERASH NE RRUGE						
1	3.17	Germim dheu seksion I lire me krahe	m ³	68		
2	An.124/4a	Germim shkembj sek. Lire me eskavator	m ³	52		
3	3.89/b	Germim dheu me mjet, toke zak, kategoria III, me shk ne mjet	m ³	905.89		
4	An164/1a	Mbushje me material te germuar me makineri	m ³	86.5		
5	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m ³	50		
SHUMA II						
PUNIME SHTRESASH NE RRUGE						
1	An152	Vijezieme shirita gjatesor 15 cm bikomponente	ml	130		
2	3.617	F.V bordure betoni 15x25	ml	300		
3	3.193/b	Shtrese zhavori lumi t=20cm me cilindrim	m ²	998		
4	3.210	Shtrese cakulli 15 cm I rrular	m ²	720		
5	3.212/b	Shtrese stabilizanti 10 cm	m ²	998		
6	An	Sperkatje emulsion bitum 1 l/m ²	m ²	720		
7	3.222/2	Shtrese binderi 6 cm	m ²	720		
8	3.226/1	Shtrese asfaltobetoni 4 cm	m ²	720		
9	An.1	Shtrese betoni C20/25 per rruge, kuneta etj	m ³	180		
10	An.2	Trajtim perfundimtar i shtreses se betonit te Trotuar/Rruge, me stampim, puder, kuarc perfshi trajtimin e prerjes se fugave	m ²	1800		
11	An.3	F.V Zgare metalike e elektrosalduar Ø 6mm/15cm ne te dy drejtim.	m ²	1800		
SHUMA III						
PUNIME KANALIZIMI UJRA SHIU						
1	3.89/b	Germim dheu me mjet, tokë zak, kategoria III, me shk në mjet	m ³	331.2		
2	3.An/1t	Tuba te brinjezuar HDPE Ø 315	ml	460		
3	An.4	Puseta shiu 60x40, h=100-150cm, me kapak kompozit	cope	30		
4	3.243	Betonim kunete monolite C 16/20	m ³	23		
SHUMA IV						
PUNIME K.U.Z						
1	3.87/a	Germim dheu kanal	m ³	124.8		
2	2.523/1	F.V. Tuba te brinjezuar PVC f=200 mm-250mm	ml	85		
3	3.An/1t	Tuba te brinjezuar HDPE Ø 315	ml	160		
4	2.575	Puset kontrolli (1x1x1.5)m	cope	8		
SHUMA V						
PUNIME MURE MBAJTES						
1	2.111/2	Mure mbajtes betoni M-200	m ³	12		
2	2.166	F V hekur betoni periodik ø6-10 mm	ton	0.2		
3	2.167	F V hekur betoni periodik ø>10 mm	ton	2.2		
SHUMA VI						



PUNIME TROTUARI				
1	3.25/a	Germim dheu themel	m ³	26.6
2	3.239	Betonim themel bordure M-100	m ³	3
3	3.617	F.V bordure betoni 15x25	ml	100
4	3.183/a	Shtrese zhavori 10 cm	m ²	596
5	3.620	Trotuar me 6 cm me pllaka betoni	m ²	596
SHUMA VII				
PUNIME NDRICIMI				
1	An.5	F. shtylla ndricimi, metalike konike h=7m LED me nje krah, perfshire te gjitha aksesoret e shtylles (krah 60mm L120x150, Ndricues 100w LED, Kabull TU 3X1.5mm, Percjelles tokezimi bakri 1x16 cu, Kontaktor trefazor 40A, FV elektroda tokezimi te xinguara, Pusete plastike 30x30, Kapak shtylle 186x45)	cope	15
2	An.6	Kabull 4x16mm Alumin	ml	546
3	An.7	Tub plastik ø63 telefoni + elektrik	ml	546
SHUMA VIII				
PUNIME GJELBERIMI				
1	An164	F.V fidane peme dekorativ	cope	15
2	3.244/1	Bordura betoni 6x12 per peme	m ²	2
SHUMA IX				
SHUMA I - IX				
T.V.SH= 20%				
SHUMA TOTALE				leke

"NET GROUP" shpk

