

PREVENTIV I PUNIMEVE**EMËRTIMI I OBJEKTIT: Sistemim asfaltim rruga e Fushes, Gjorme (LOTI - I)
(km 00+000 - km 01+000)**

| <u>Nr-</u> | <u>Analize</u> | <u>Emërtimi</u> | <u>Njësia</u> | <u>Sasia</u> | <u>Çmimi</u> | <u>Vlera</u> |
|----------------------|----------------|---|----------------|--------------|----------------------|--------------|
| I | | PUNIME GERMIM MBUSHJE | | | | |
| 1.1 | | Germim dheu me ekskavator zingjir, 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne toke | m ³ | 666.0 | | |
| 1.2 | | Transport dheu me auto deri 2.0 km | m ³ | 666.0 | | |
| 1.3 | | Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke te bute | m ³ | 47.8 | | |
| Shuma 1 | | | | | | |
| II | | SHTRESA RRUGORE | | | | |
| 2.1 | | Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri | m ² | 4,000.0 | | |
| 2.2 | | Shtrese binderi me granil gur kave,6cm,me makineri | m ² | 4,000.0 | | |
| 2.3 | | Shtrese stabilizant 15 cm | m ² | 3,491.0 | | |
| Shuma 2 | | | | | | |
| | | | | | SHUMA (1)+(2) | |
| | | | | | T.V.SH. 20% | |
| SHUMA ME TVSH | | | | | | |