



REPUBLIKA E SHQIPËRISË

PREVENTIVI

“Ndertimi i Trotuarit te ri ne lagjen “Xhenjo”

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
<b>I</b>	<b>PUNIME PER TROTUARIN</b>					
1	An1	Germim ne toke te zakonshme seksion i detyruare ,me shk ne mjet	m <sup>3</sup>	800,00		
2	2.37/3a	Transport materiale ndertimi, dheu me auto deri 3.0 km	m <sup>3</sup>	826,00		
3	3,62	Trotuar, me 6 cm beton, me pllaka	m <sup>2</sup>	2109,00		
4	3.212/b	Shtrese stabilizant t=10cm	m <sup>2</sup>	2109,00		
5	3.205/2	Shtrese zhavori lumi t=20cm, perhapur e ngjeshur me makineri	m <sup>2</sup>	2109,00		
6	3.616/a	F V bordura betoni 15x30cm	m	1054,00		
7	3,616	F V bordura betoni 12x25cm	m	1038,00		
8	3.243/1	Struktura te holla monolite betoni C 16/20	m <sup>3</sup>	65,00		
9	An - 23	Pusete shiu 40 x 60, h = 100 cm, me kapak gize	cope	45,00		
10	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	44,00		
11	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	1056,00		
12	2,258	Nenshtrese zhavori(mbi tubin e brinjezuar)	m <sup>3</sup>	260,00		

13	2.523/1	F.V Tuba PVC f=200 mm te brinjezuar(per vendosjen e shtyllave)	ml	31,00		
14	2,261	Shtrese rere (nen dhe mbi tubacione + kompaktesim)	m <sup>3</sup>	92,00		
15	3.243/1	Struktura te holla monolite betoni C 16/20(per fiksimin e shtyllave)	m <sup>3</sup>	15,00		
16	2.1a	Germim dheu me krah e transport k dore 10m,kat IV(per bazamentin e shtyllave dhe pusetat)	m <sup>3</sup>	27,00		
17	An2	Tub PVC fleksibel Ø 75 mm	ml	1083,00		
<b>Shuma I</b>						
		<b>SHUMA TOTALE</b>				
		<b>TVSH</b>	<b>20%</b>			
		<b>TOTALI</b>				

**DREJTORIA E PLANIFIKIMIT TE TERRITORIT DHE ZHVILLIMIT RURAL**

**HARTOI:**

**ING. ALBAN LAÇI**

**ING. JURGEN MARKU**

