

PREVENTIVI I PUNIMEVE

Objekti: Sistemim Asfaltim Rruga Sharrdushk - Kryevidh L= 1400 metra

Nr.	Nr. i Analize	Zerat e punimeve	Njësia	Sasia	Çmimi(Lekë)	Vlera (Lekë)
1	3.104/b	Germim dheu me ekskavator zingjir, 0.5 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria IV, me shk ne mjet.	m3	320		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m3	320		-
3	An	Skarifikim shtrese asfalti me makineri h=10cm.	m2	800		-
4	An	Frezim shtrese asfalti me makineri h=1-3cm.	m2	5,600		-
5	An.164/1a	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri.	m3	160		-
6	3.212	Shtrese çakelli t=10/15cm, makadam, perhapur e ngjeshur makineri.	m2	120		-
7	3.212/b	Shtrese stabilizant t=10cm.	m2	1,500		-
8	3.229/2	Shtrese binderi me zall lavatrice, 6cm, me makineri	m2	1,500		-
9	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m2	6,300		-
		Shuma pa TVSH				-
		TVSH 20%				-
		Vlera totale me TVSH				-