

PREVENTIV

Objekti: Rikonstruksion i palestres se shkolles 9-vjecare
"Migjeni" Puke

NR	ANALIZA	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	ÇMIMI (Leke)	SHUMA (Leke)
		1. Punime prishje				
1	2.276/d	Dizermim parketi	m ²	278		
2	3.370/d	Dizermim dritaresh	m ²	40.2		
3	2.310/d	Prishje suvatimesh	m ²	912		
4	2.426/3	Prishje shtresa betoni	m ³	15		
5	2.37/4a	Transport materiale ndertimi, dheu me auto deri 4.0 km	m ³	42.36		
		Shuma 1	Leke			
		2. Punime Ndertimi				
1	2.200	Shtrese lluster cemento 1:2, t = 20 mm	m ²	10		
2	2.196	Hidroizolim me emulsion bitumi dhe 1 shtrese k katrama	m ²	278		
3	3.243/1	Struktura te holla monolite betoni C 16/20	m ³	28		
4	an	Shtrese me polisport ,primer PU rere kuarci, PU Binder SBR granulometri Gome, PU stuko, Elastoturf 51A12,Elastomark	m ²	278		
5	2.310	Suva brenda mur tulle h~4m me krah, llaç perzier M 25	m ²	600		
6	2.300	Suva solete h ~ 4 m me drejtues, me krah	m ²	312		
7	2.404	Boje hidroplastike	m ²	912		
8	2.401	Boje vaji siperfaqe metalik	m ²	25		
9	2.375/1	F V dritare d/alumini plastike me dopio xham	m ²	40		
10	An126	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm, Termoplastike (paste)	ml	133		
		Shuma 2	Leke			
		3. Punime elektrike				
1	480/3	F.V tub plastmasi Ø 22 ~ 26 mm	ml	200		
2	2.487/b	F.V kuti suport pllaket 4 modular	cope	5		
3	2.481/2	F.V percjelles PV-500 Ø 2.5 mm ²	ml	600		
4	2.485/e	F.V priza shuko jashte murit 2P+T IP=54 "Vimar"	cope	4		
5	2.485/1	F.V Çeles 1 polar 220V 10A "Vimar"	cope	6		
6	2.487	F.V Kutiderivacioni plastike	cope	12		

7	2. a-132	Ndricues tavanor fluoreshente 1x40w	cope	33		
		Shuma 3	Leke			
		Totali (1+2+3)	Leke			
		tvsh 20%	"			
		Totali i Preventivit	Leke			