

PREVENTIV ZBATIMI

Objektit: Ndërtim Ure Perroi I Bullomes, Fshati Kalace, NJ.A. Ndroq

Nr	Anal	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Vlera
1	3.2	Prerje bime te vogla ø-10cm	m2	110		
2	2.426/5	Prishje mure ballnat ekz	m3	55.5		
3	2.426/4	Prishje soleta b/a	m3	5.4		
4	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m3	265		
5	3.158/5a	Transport dheu me auto deri 5.0 km	m3	265		
6	An-8	Mbushje me cakell	m3	245		
7	3.248	Struktura monolite betoni me çakell C 30/37,tombino	m3	35		
8	3.247	Struktura monolite betoni me çakell C 25/30,sperona,portale,soleta rakorduese	m3	87		
9	3.24	Beton themeli C 12/15,shtresa e tombinove	m3	9		
10	3.288	F V hekur betoni i zakonshem Ø > 12mm per tombino box+sperona	ton	12.95		
11	3.624	H / Izolim me emulsion, 2 duar bitum per tombino box	m2	85		
12	An	Handrail + aksesoret	ml	15		
13	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m2	80		
14	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m3	10		
		SHUMA				
		Fondi Rezerve 3%				
		SHUMA PA TVSH				
		T.V.SH 20%				
		TOTALI				