

PREVENTIV

Objekti: " Sistemim, asfaltim i rrugës Oblike – Pallate "(Faza II)

Nr	Nr.Anal.	Pershkrimi i Punimeve	Nj.	Sasia	Çmimi	Vlera
A	AKSI 2 km 0+087 - km 0+175, L=88m					
1	Punime per rrugen					
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	140		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	155		-
3	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	125		-
4	3.212/b	Shtrese stabilizant t=10cm	m ²	425		-
5	3.229/1	Shtrese binderi me zall lavatrice t=5cm me makineri	m ²	380		-
6	3.231/1	Shtrese asfaltobetoni, me zall lavatrice , 3 cm me makineri	m ²	380		-
7	2.426/3	Prishje shtresa betoni	m ³	15		-
Shuma 1						-
2	Punime per trotuare					
1	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	120		-
2	2.261	Shtrese rere 4 cm	m ³	4.5		-
3	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m ²	120		-
4	2.262/4	Shtrese betoni C 16/20 t=10 cm per kunete dhe trotuar betoni	m ³	41		-
5	3.617	F V bordura betoni 15x25 cm	ml	190		-
6	2.262/3	Shtrese betoni C 12/15 per fiksimin e bordurave	m ³	5		-
Shuma 2						-
SHUMA A						-
B	AKSI 3 km 0+000 - km 0+095, L=95m					
1	Punime per rrugen					
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	250		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	260		-
3	3.198	Cilindrim kasonete me rrul	m ²	660		-
4	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	165		-
5	3.212/b	Shtrese stabilizant t=10cm	m ²	660		-
6	3.212/b	Shtrese stabilizant t=10cm per bankine		85		-

7	3.229/1	Shtrese binderi me zall lavatrice t=5cm me makineri	m ²	660		-
8	3.231/1	Shtrese asfaltobetoni, me zall lavatrice , 3 cm me makineri	m ²	660		-
9	2.426/3	Prishje shtresa betoni	m ³	10		-
Shuma 1						-
2 Punime per trotuare						
1	3.620	Trotuar, me 6 cm beton, me pllaka	m ²	165		-
2	2.261	Shtrese rere 4 cm	m ³	7		-
3	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m ²	165		-
4	2.262/4	Shtrese betoni C 16/20 t=10 cm trotuar betoni	m ³	35		-
5	3.617	F V bordura betoni 15x25 cm	ml	180		-
6	2.262/3	Shtrese betoni C 12/15 per fiksimin e bordu	m ³	12		-
Shuma 2						-
SHUMA B						-
C PUNIME PER K.U.B						
1	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m ³	45		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	45		-
3	2.261	Shtrese rere 10 cm	m ³	9		-
4	M3.An-8	Mbushje me cakell	m ³	11		-
5	3.An/1t	F V tuba te brinjeluar HDPE SN8 d=315 mm	ml	80		-
6	M2.An-22	Pusete b/a shiu 40 x 40 cm, h = 100 cm, me kapak zgare hekuri	cope	3		-
SHUMA C						-
D PUNIME SINJALISTIKE						
1	An 151	Vijezim me boje bikomponente	m ²	65		-
2	An97	F V tabela rrugore te ndryshme	cope	10		-
SHUMA D						-
Shuma A + B + C + D						-
Fondi Rezerve 5%						-
Shuma pa TVSH						-
TVSH 20%						-
Shuma me T.V.SH						-

PREVENTIVOI
"LENI-ING" sh.p.k.
Ing. NIKOLL PALUCA