

**PREVENTIV**  
**RIKONSTRUKSION RRUGA "MENDAFSHIT"**

Nr	Nr AN	EMERTIMI I PUNIMEVE	Njesia	Sasia	Cmimi	Vlera
	<b>I</b>	<b>Punime me Shtresat e Rruges Aksi Kryesor</b>				
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne miet	m <sup>3</sup>	250		-
2	3.158/5a	Transport dheu me auto deri 5 km	m <sup>3</sup>	250		-
3	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m <sup>2</sup>	670		-
4	3.212/b	Shtrese stabilizanti 10cm per rrugen	m <sup>2</sup>	670		-
5	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri per kunete	m <sup>3</sup>	15		-
6	3.228/1	Shtrese binderi me zall lavatrice,4cm,me makineri	m <sup>2</sup>	670		-
7	3.231/1	Shtrese asfaltbetoni me zall lavatrice, 3cm, me makineri	m <sup>2</sup>	670		-
8	3.240	Struktura monolite betoni C 12/15 per kuneta	m <sup>3</sup>	8.0		-
		<b>shuma I</b>				-
	<b>II</b>	<b>Punime ne Trotuare</b>				
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne miet	m <sup>3</sup>	25		-
2	3.158/5a	Transport dheu me auto deri 5 km	m <sup>3</sup>	25		-
3	3.239	Struktura monolite betoni C 7/10 per bordura	m <sup>3</sup>	3.4		-
4	3.240	Struktura monolite betoni C 12/15 per trotuare	m <sup>3</sup>	10.0		-
5	3.617	F V bordura betoni 15x25 cm	ml	340.0		-
6	3.183/b	Shtrese zhavor lumi t=15cm per trotuar betoni	m <sup>2</sup>	100		-
		<b>shuma II</b>				-
	<b>III</b>	<b>Punime per KUB , KUZ</b>				
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne miet	m <sup>3</sup>	100		-
2	3.158/5a	Transport dheu me auto deri 5 km	m <sup>3</sup>	100		-
3	2.261	Shtrese rere per tuba	m <sup>3</sup>	35		-
4	2.258	Nenshtrese zhavori per kanale	m <sup>3</sup>	60		-
5	An - 19	Pusete shkarkimi b/a, 80 x 80 cm, h = 100 cm	cope	7		-
6	An.	Mbingritje pusete shkarkimi me kapak gize D=60cm	cope	3		-
7	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm	ml	145		-
8	3.An/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm	ml	145		-
9	An	F V tuba te brinjezuar HDPE SN8 d=200 mm	ml	80		-
10	An - 23	Pusete b/a shiu 40 x 60, h = 100 cm, me kapak gize	cope	8		-
11	An	Lidhje me rrjetin ekzistues te linjave KUB, KUZ	cope	2		-

		<b>shuma III</b>				-
	<b>IV</b>	<b>Punime per UJESJELLES</b>				
1	3.89/a	Germim dheu me ekskavator 0.25 m <sup>3</sup> , toke zak, kategoria III, me shk ne mjet	m <sup>3</sup>	15		-
2	3.158/5a	Transport dheu me auto deri 5 km	m <sup>3</sup>	15		-
3	2.261	Shtrese rere per tuba	m <sup>3</sup>	6		-
4	2.258	Nenshtrese zhavori	m <sup>3</sup>	11		-
5	An - 19	Pusete b/a 80 x 80, h = 100 cm, me kapak gize	cope	4		-
6	2.491/e	F.V Tuba e rakorderi ujesjellesi PE d=50mm, t = 3.7 mm, PN 10	ml	60		-
7	2.491/c	F.V Tuba e rakorderi ujesjellesi PE d=32mm, t = 2.4 mm, PN 10	ml	32		-
8	An	Lidhje me rrjetin ekzistues te linjes se Ujesjellesit	cope	1		-
		<b>shuma IV</b>				-
	<b>V</b>	<b>SINJALISTIKA E SIGURIA</b>				
1	An 151	Vizime me boje bikomponente	m <sup>2</sup>	36		-
2	An 158	FV tabela te ndryshme rrugore D=60cm	cope	2		-
		<b>shuma V</b>				-
		<b>SHUMA(I deri V)</b>				-
		<b>Fond Rezerve 2%</b>				-
						-
		<b>TVSH 20%</b>				-
		<b>TOTAL</b>				-

**PREVENTIVOI**  
**"Novatech Studio"shpk**