

PREVENTIV

OBJEKTI: "Nderhyrje ne infrastrukturen e brendeshme Ksamil"

INVESTITOR: Bashkia Sarande

Nr.	NR.ANALIZE	Emërtimi i punimeve	Njësia	Sasia	Çmimi	Vlefte
A		Rr. Magdalena (B=5m , L= 270ml)				
1		Rrafshim ,nivelim , skarifikim t=10cm	m2	1350		
2		Shtrese stabilizant t=15cm	m2	1350		
3		Shtrese binderi me granil gur kave,6cm,me makineri	m2	1350		
4		Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri , b=2x0.5m , per bankinat anesore	m2	220		
		Shuma 1				
B		Degezim ``Naim Frasheri - Deti Jon`` (B=5m , L= 70ml)				
1		Rrafshim ,nivelim , skarifikim t=10cm	m2	350		
2		Shtrese stabilizant t=15cm	m2	350		
3		Shtrese binderi me granil gur kave,6cm,me makineri	m2	350		
4		Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri , b=2x0.5m , per bankinat anesore	m2	70		
		Shuma 2				
C		Rr. SAMI FRASHERI (B=5m , L= 200ml)				
1		Rrafshim ,nivelim , skarifikim t=10cm	m2	1085		
2		Shtrese stabilizant t=15cm	m2	1085		
3		Shtrese binderi me granil gur kave,6cm,me makineri	m2	1085		
4		Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri , b=2x0.5m , per bankinat anesore	m2	150,0		
		Shuma 3				
D		Rr. Liqeni (B=3m , L= 350ml)				
1		Rrafshim ,nivelim , skarifikim t=10cm	m2	1050		
2		Shtrese stabilizant t=15cm	m2	1050		
3		Shtrese binderi me granil gur kave,6cm,me makineri	m2	1050		
4		Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri , b=2x0.5m , per bankinat anesore	m2	250		
		Shuma 4				
E		Rr. ALPET (B=5m , L= 550ml)				
1		Rrafshim ,nivelim , skarifikim t=10cm	m2	2750		
2		Shtrese stabilizant t=15cm	m2	2750		
3		Shtrese binderi me granil gur kave,6cm,me makineri	m2	2750		
4		Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri , b=2x0.5m , per bankinat anesore	m2	350		
		Shuma 5				
H		PUNIME KANALIZIMI				
1		Pastrim i linjave te KUZ-ve	ml	142		
		Shuma 6				

	Shuma1-6		
	T.V.SH	20%	
	Totali		

Preventivoi

Miratoi