

PREVENTIV

EMERTIMI I OBJEKTIT : "RIKONSTRUKSION ISH SHKOLLA VETERINARE "

N.r	Nr. Anal.	Pershkrimi	Njesia	Sasia	Çmimi	Vlera
		I - PUNIME SHTRESASH				
1	2.267/1	Shtrese me pllaka porcelanat ,ne ambjentet sanitare	m ²	76.0		
2	2.326	Veshje me pllaka amjentet sanitare	m ²	280.0		
3	2.196/c	Hidroizolim me dy shtresa llaci me baze cemento. Pergatitur nga dy komponente A+B (tualetet)	m ²	93.0		
4	2.267/b	Shtrese me pllaka grez importi 40 x 40 cm	m ²	505.0		
5	2.324b	Plintuse grez h = 10 cm	m ²	663.0		
		Shuma 1				
		II - PUNIME DYER DRITARE				
1	An+2.383/1	F V dyer te brendeshme Mdf	m ²	16.4		
		Shuma 2				
		III- PUNIME BOJATISJE				
1	2.404	Boje hidroplastike ,Lyerje Brenda	m ²	507.0		
		Shuma 3				
		IV- PUNIME SISTEMIMI SHESHI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m ³	272.0		
2	2.37/5b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m ³	272.0		
3	3.243/1	Struktura te holla monolite betoni C 16/20 10cm	m ³	59.0		
4	2.166	F V hekur betoni periodik Ø 6 - 10 mm	ton	4.0		
5	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur makineri	m ²	585.0		
6	An164	F.V. Fidane Peme dekorative	cope	6.0		
7	An168	F.V shkurre dekorative Juniperus V.18 grup 3 cdo 6.6m	cope	18.0		

8	Man 3.643	Mbjellje bari+dhe vegjetal	m ²	380.0		
9	An.164/1a	Mbushje me material te germuar me pare	m ³	133.0		
		Shuma 4				
		V- PUNIME NE RRJETIN E FURNIZIMIT ME UJE				
1	3.212/b	Shtrese stabilizant t=10cm	m ²	19.0		
2	3.210	Shtrese çakelli mbeturine kave, perhapur e ngjeshur makineri t=15cm x 2 here (30cm)	m ³	6.0		
3	2.501	F.V WC allafrenga importi	cope	17.0		
4	2.495	F.V lavapjate importi porcelani (Lavaman per femije 0-1 vjec)	cope	14.0		
5	An	F.V Bolier 30 l importi	cope	8.0		
6	An - 15	F V bolier 80 liter, uje te ngrohte	cope	4.0		
		Shuma 5				
		Punime elektrike				
1	An	F.V kabell ABC 4 x50 mm ² , 0.6 /1 KV	ml	200.0		
2	An	Qafore	cope	6.0		
3	3.520	FV shtylla centrifuguara b/a M-300 linja 0.4-10kv,traktor, ndermj, NH-7m, 130/243/5	cope	2.0		
4	An	Tirant per kabell 4x50mm ²	cope	6.0		
5	An	Ndricules Tip LED 45W 5500lm, 4000K 60x60cm jashta murit	cope	215.0		
6	An	Ndricules Tip LED 48W 6000lm, 4000K 120x30x5cm jashta murit	cope	32.0		
7	An	Ndricules rrethor D=175mm, LED 22W, 4000K	cope	21.0		
8	An	Ndricules evakuimi me llampe 1*11w ip40	cope	80.0		
9	An-5.2	FV.Pusete betoni me kapak metalik 50x50x50	cope	1.0		
10	An-5,4	F.v. Pusete plastike 30x30x30	cope	5.0		
11	An-6.3	F.v. Tub kavidot 40mm	ml	55.0		
12	An-17.2	F.v. Shtylle konike Zn h=3m	cope	5.0		
13	2,a-73	FV.Elektroda zingate T 1.5m	cope	5.0		
14	An	Ndricules TOCIA SAP-T 70 oborr	cope	5.0		
15	An -M.16	Montim Ndricules ne shtylle	cope	5.0		

			Shuma 6			
		SISTEMI I NGROHJES				
	An	Punime mekanike Total (kondicionim)				
1	An	F vendosje kondensionera 24000 btu	cope	8.0		
2	An	F vendosje kondensionera 18000 btu	cope	6.0		
3	An	F vendosje kondensionera 12000 btu	cope	1.0		
4	An	F vendosje kondensionera 9000 btu	cope	3.0		
			Shuma 7			
		Te ndryshme				
1	An - 22	Pusete b/a shiu 40 x 40 cm, h = 100 cm, me kapak zgare hekuri	cope	26.0		
2	An	F.V porte metalike dekorative	m2	17.0		
3	2.413	F.V zgara dekorativa hekuri me figuracion mesatare	ton	2.7		
4	2.297/b	Tavan i varur me pllaka gipsi 60x60cm	m2	88.0		
5	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m2	139.0		
6	2.276	Shtrese parketi	m2	68.0		
7	2.267/1	Shtrese me pllaka porcelanat importi	m2	84.0		
8	2.88	Mur me blloqe betoni t=20cm deri 3m me llaç perzier M 15	m3	18.0		
9	2.35	Suva xokoli me granil e çimento te zakonshme me spruco	m2	224.0		
10	2.404/1	Boje hidroplastike importi cilesi e I-re	m2	224.0		
			Shuma 8			
		SHUMA PA TVSH				
		TVSH 20%				
		SHUMA TOTALE				

Preventivoi :

Ing. Florinda HILAJ

Ing. Elsid SADIKU