

OBJEKTI: NDERTIM I RRJETIT TE HIDRANTEVE KRASTE

NR	Manuali	EMERTIMI I PUNIMIT	NJESIA	SASIA	CMIMI	VLERA
I		Linja e dergimit				
1	anal	Prerje asfalti me makine prerese	ml	60		
2	3.89/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m3	932		
3	3.87/a	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne toke	m3	451		
4	2.37/4b	Transport materiale ndertimi, dheu me auto deri 9.0 km	m3	1146		
5	2.261	Shtrese rere (per mbrojtje tubi)	m3	162		
6	2.491/i	F.V Tuba e rakorderi ujesjellesi PE d=125mm, t = 8.6 mm, PN 10	ml	2973		
7	2.258	Nenshtrese zhavori	m3	164		
8	3.47/1b	Mbushje, rafshim,ngjeshje me tokmak elektrik, cdo 30 cm, toke zak	m3	164		
9	3.205	Shtrese zhavori lumi t=10cm, perhapur e ngjeshur me makineri	m2	60		
10	3.207	Shtrese çakelli t=10cm, perhapur e ngjeshur me makineri	m2	60		
11	3.212/b	Shtrese stabilizant t=10cm	m2	60		
12	An	Sperkatje me emulsion bituminoz 1 l/m2	m2	60		
13	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri	m2	60		
14	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri	m2	60		
15	2.511	F.V hidrante Ø 80 mm	cope	7		
16	An - 23	Pusete b/a per hidrantet 40 x 60, h = 100 cm, me kapak gize	cope	7		
		Shuma I				
II		STACIONI I POMPAVE				
1	3.244	Struktura monolite betoni C 20/25 per bazament	m3	1.95		
2	an.	F:V pompe Centrifugale 120kw	cope	1		
3	an.	F:V rakorderi	leke	1		
4	an.	F:V Panel komandimi	leke	1		
		Shuma II				
		SHUMA (I+II)				
		T.V.SH.	20%			
		TOTALI	LEKE			