



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

OBJEKTI : Ndertim Rruga " 28 Nentori + 1 Maji " Babrru Koder, Bashkia Kamez, Ltot= 1648 ml

Rruga 28 Nentori Ltot = 729 m L1 = 531 m , B1= 7 m , Basfalt = 4.5m + kunetelx0.5 m+ trotuar 1.3+0.7 m + L2= 118m ,
B2=4 m basft=4.0, L3= 80 , B=4m asflat (seg tek Rr. Sali Myftia)

A	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	481.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	481.5		
3	An. 8	Mbushje me çakell shkembor	m ³	319.95		
4	3.211	Shtrese çakelli T=20cm	m ²	3199.5		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	3199.5		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	3199.5		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	3199.5		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	176.55		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	9.71		
10	An.	Ngritje pusete+kapak gize	cope	7		
11	An.	Spostim shtyllash	cope	14.00		
12	2/426/2	Prishje mure me blloqe + transport +pastrim me makineri	m ³	321		
13	An.152	Vizime me boje bikomponente 15cm	ml	1733.5		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	293.2		
2	3.158/5a	Transport çakelli me auto 5km	m ³	293.2		
3	3 An. 8	Mbushje me çakell shkembor	m ³	146.6		
4	3.an/1t	F.V. Tuba I brinjzuar Ø 315	ml	733		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	26.75		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	15.00		
SHUMA II						
III PUNIME KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	445.3		
2	3.158/5a	Transport çakelli me auto 5km	m ³	445.3		
3	3 An. 8	Mbushje me çakell shkembor	m ³	222.6		
4	3.an/1t	F.V. Tuba I brinjzuar Ø 315	ml	685		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	18.00		
SHUMA III						
IV PUNIME TROTUARE(1x1.3x1x0.7)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	297.5		
2	3.158/5a	Transport dheu me auto 5km	m ³	297.5		
3	3 An. 8	Mbushje me çakell shkembor	m ³	148.75		
4	3.208	Shtrese çakelli T=10cm	m ²	1190.0		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m ²	1190.0		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	1070		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	32.1		

8	2.109/2	Shtrese betoni trotuari	m ³	119		
			SHUMA IV			
V	PUNIME VEPRARTI (MURE MBAJTËS)					
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	107		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	107		
3	3.243	Struktura monolite betoni C 16/20 per muret mbajtese	m ³	375		
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	1.50		
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	2.2		
			SHUMA V			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	550		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	550		
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	15		
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1		
5	3.139	Germime dheu me ekskavator me goma	m ³	110		
6	3.158/5a	Transport dheu me auto 5km	m ³	110		
7	2.261	Mbushje me rere	m ³	44		
8	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	66		
			SHUMA IV			
			SHUMA A			

OBJEKTI : Ndertim Rruga "Rruga 1 Maji " Babrru Koder , Bashkia Kamez
Rrugal Maji Ltot =919 m L1 = 769 m , B1= 7 m , Basfalt = 4.5m + kunete 1x0.5 m+ trotuar 1.3+0.7 m +
L2= 151m, B2= 5 m basft=4.0+ 2 x 0.5 kunete

					L1=	768
					L2=	151
B	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I	PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	587.52		
2	3.158/5a	Transport dheu me auto 5km	m ³	587.52		
3	An. 8	Mbushje me çakell shkembor	m ³	406		
4	3.211	Shtrese çakelli T=20cm	m ²	4060		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	4060		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	4060		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	4060		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	240.00		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	9.60		
10	An.	Ngritje pusete+kapak gize +pastrim me makineri	cope	7		
11	An.	Spostim shtyllash	cope	16.00		
12	2/426/2	Prishje mure me blloqe + transport	m ³	414.72		
13	An.152	Vizime me boje bikomponente 15cm	ml	2222		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
			SHUMA I			
II	PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	307.2		
2	3.158/5a	Transport çakelli me auto 5km	m ³	307.2		
3	3 An. 8	Mbushje me çakell shkembor	m ³	153.6		
4	3.an/1t	F.V. Tuba I brinjzuar Ø 315	ml	768		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	38.4		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	21.94		
			SHUMA II			
III	PUNIME KUN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	499.2		
2	3.158/5a	Transport çakelli me auto 5km	m ³	499.2		
3	3 An. 8	Mbushje me çakell shkembor	m ³	249.6		
4	3.an/1t	F.V. Tuba I brinjzuar Ø 315	ml	768		

5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	16.00		
SHUMA III						
IV	PUNIME TROTUARE(1x1.3x1x0.7m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	220.0		
2	3.158/5a	Transport dheu me auto 5km	m ³	220.0		
3	3 An. 8	Mbushje me çakell shkembor	m ³	110.0		
4	3.208	Shtrese çakelli T=10cm	m ²	1100.0		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m ²	1100.0		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	1536		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	46.08		
8	2.109/2	Shtrese betoni trotuari	m ³	110		
SHUMA IV						
V	PUNIME VEPRA ARTI (MURE MBAJTES)					
1	3.105/a	Germim dheu me ekskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	154		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	154		
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	315.62		
	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	3.56		
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	5.6		
SHUMA V			ton			
IV	PUNIME PER NDRICIMIN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	640		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndrçimin	ml	640		
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	17		
4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1		
5	3.139	Germime dheu me ekskavator me goma	m ³	128		
6	3.158/5a	Transport dheu me auto 5km	m ³	128		
7	2.261	Mbushje me rere	m ³	51.2		
8	Man 3 An. 8	Mbushje me cakull shkembor (kanal)	m ³	76.8		
SHUMA IV						
SHUMA B						
SHUMA A-C						
TVSH 20%						
TVSH TOTALE						

V.O. Preventivi eshte hartuar ne baze te vkm nr 629 date 15.07.2015

Preventivues :

Ing. Hajredin MURGU



Drejtori i Pergjithshem

Z.Elvis Gjika



Drejtori P.I-se

Ing. Flora MUÇA



**MIRATOI
Rakip SULI**

KRYETAR

