

PREVENTIVI

REHABILITIMI DHE NDERTIMI I URES GESHTENJE L=27M KUKES

VLERESUAR SIPAS VKM Nr. 629 Dt.15.07.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
PUNIME TE NDRYSHME NDERTIMI						
1	2.26a	Germim dhe themele e plinta me b=2m, ekskavator me goma 0.25m ³ ,shkarkimi ne auto	m ³	208.00		0.00
2	2.37/5a	Transport materiale ndertimi, dheu me auto deri 5.0 km	m ³	148.00		0.00
3	3.212/d	Shtrese stabilizant t=20cm(shtresa nen themel)	m ²	65.00		0.00
5	3.243	Struktura monolite betoni C 16/20(shtresa nen themel)	m ³	6.50		0.00
6	An35	F.V - parapet I njeanshem per beton (ø 60)	ml	60.00		0.00
7	2.117/lb	Kollona b/a monolite C 25/30 h - 4m	m ³	45.00		0.00
8	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	4.95		0.00
9	2.167	Hekur betoni ø>10 mm	ton	8.41		0.00
10	2.262/4b	Pllake themeli, trare e bazamente b/a C 25/30	m ³	72.00		0.00
11	2.122/1a	Soleta te plota b/a C 20/25 t = 30 cm, h ~ 4m	m ³	57.50		0.00
12	An-8	Mbushje me cakell pas mureve	m ³	150.00		0.00
13	3.332	Gabiona me rrjete teli te zinguar, gure kave 1x1x1.5 m	m ³	60.00		0.00
14	3.331	Gabiona me rrjete teli te zinguar e gure kave 1x1x1 m	m ³	40.00		0.00
SHUMA I						
TVSH			20%			
TOTALI						

Punoj: Ing. Xhem Neçi Lic. K1034/2

PREVENTIVI

REHABILITIMI DHE NDERTIMI I URES ORGJOST L=36M KUKES

VLERESUAR SIPAS VKM Nr. 629 Dt.15.07.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
I	PUNIME TE NDRYSHME NDERTIMI					
1	An-1	Çmontim I dyshemes ekzistuese	m ³	7.23		
2	An-2	F.V derrasa dyshemeje me trashesi 5 cm dhe gjatesi 4m	m ³	7.23		
3	An-3	F.V morseta per bashkim me panelin	cope	100.00		
4	2.400	Boje vaji siperfaqe druri	m ²	353.00		
5	2.401	Boje vaji siperfaqe metalike	m ²	993.00		
	SHUMA II					
	TVSH		20%			
	TOTALI					

Punoj: Ing. Xhem Neçi Lic. K1034/2

PREVENTIVI

REHABILITIMI DHE NDERTIMI I URES CERNALEVE L=21M KUKES

VLERESUAR SIPAS VKM Nr. 629 Dt.05.07.2015

Nr.	Analize	Emertimi i Punimeve	Njesia	Sasia	Çmimi	Shuma
-----	---------	---------------------	--------	-------	-------	-------

I	PUNIME TE NDRYSHME NDERTIMI					
1	An-1	Çmontim I elementeve ekzistuese	ton	25.00		
2	An-2	F.V derrasa dysHEMEJE me trashesi 5 cm dhe gjatesi 4m	m ³	3.12		
3	2.181	Konstruksione metalike te perbera	ton	17.94		
4	2.167	F V hekur betoni i periodik Ø > 10mm	ton	1.50		
6	2.117/1	Kollona b/a monolite C -16/20 h ~ 4m	m ³	8.00		
4	2.400	Boje vaji sipërfaqe druri	m ²	189.60		
5	2.401	Boje vaji sipërfaqe metalike	m ²	463.00		
SHUMA III						
	TVSH		20%			
TOTALI						

Punoi: Ing. Xhem Neçi Lic. K1034/2



