



REPUBLIKA E SHQIPERISE
BASHKIA KAMEZ
PREVENTIV

REHABILITIM RRUGET E BLOKUT PASKUQAN 2

OBJEKTI :Rehabilitim Rruget : Rruga Hazis Ndreu + Rruga Filip Shiroka + Rruga Asdreni + Rruga Vehbi Dibra + Rruga Irfan Strazimiri + Rruga Demir Gashi + Rruga Dom Nikoll Kaçorri + Rruga Dede Plani + Rruga Iljaz Pash Dibra , Paskuqan 2 Fushe , Njesia Administrative Paskuqan , Bashkia Kamez

OBJEKTI : Ndertim Rruga "Rruga Azdreni " Paskuqan 2 , Bashkia Kamez

B=6 m , basfalt=4.5 kunet=0.5m , trotuar 1x1 m

L= 260

G	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera	
I		PUNIME NE RRUGE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA			
1	3.139	Germim dheu me eskavator	m ³	234			
2	3.158/5a	Transport dheu me auto 5km	m ³	234			
3	An. 8	Mbushje me çakell shkembor	m ³	117			
4	3.211	Shtrese çakelli T=20cm	m ²	1170			
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1170			
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1170			
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1170			
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	97.50			
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	2.44			
10	An.	Ngritje pusete+kapak gize	cope	2			
11	An.	Spostim shtyllash	cope	6.00			
12	2/426/2	Prishje mure me blloqe + transport	m ³	156			
13	An.152	Vizime me boje bikomponente 15cm	ml	650			
14	An.96	Tabele sinjalistike 60-90cm	cope	4			
		SHUMA I					
II		PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA			
1	3.139	Germim dheu me eskavator	m ³	104			
2	3.158/5a	Transport dheu me auto 5km	m ³	104			
3	3 An. 8	Mbushje me çakell shkembor	m ³	52			
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	260			
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	13			
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	7.00			
		SHUMA II					
II		PUNIME NE KUN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA			
1	3.139	Germim dheu me eskavator	m ³	67.4			
2	3.158/5a	Transport çakelli me auto 5km	m ³	67.4			
3	3 An. 8	Mbushje me çakell shkembor	m ³	94			
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	260			
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	5.00			
		SHUMA II					
III		PUNIME TROTUARE(1x1 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA			
1	3.139	Germim dheu me eskavator	m ³	93.75			
2	3.158/5a	Transport dheu me auto 5km	m ³	93.75			
3	3 An. 8	Mbushje me çakell shkembor	m ³	37.5			
4	3.208	Shtrese çakelli T=10cm	m ²	212.5			
5	3.212/a	Shtrese stabilizanti ne trotuar T=5 cm	m ²	212.5			
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	450			
7	2/262/4	Beton per fiksime bordure C16/20	m ³	13.5			
8	2.109/2	Shtrese betoni trotuari	m ³	21.25			

			SHUMA III			
IV			PUNIME PER NDRICIMIN			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø 80 per ndricimin	ml	250		
2	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	7		
3	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1		
			SHUMA IV			
			SHUMA G			

OBJEKTI : Ndertim Rruga " Filip Shiroka " Paskuqan 2 Koder , Bashkia Kamez

B=6 m , basfalt=4.0 kunet=2x0.5m , trotuar 1x1 m

L= 310

H	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	279		
2	3.158/5a	Transport dheu me auto 5km	m ³	279		
3	An. 8	Mbushje me çakell shkembor	m ³	124		
4	3.211	Shtrese çakelli T=20cm	m ²	1240		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1240		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1240		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	1240		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	93.00		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	2.33		
10	An.	Ngritje pusete+kapak gize	cope	7		
11	An.	Spostim shtyllash	cope	6.00		
12	2/426/2	Prishje mure me blloqe + transport	m ³	186		
13	An.152	Vizime me boje bikomponente 15cm	ml	930		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
			SHUMA I			
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	124		
2	3.158/5a	Transport dheu me auto 5km	m ³	124		
3	3 An. 8	Mbushje me çakell shkembor	m ³	62		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	310		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	31		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	8.86		
			SHUMA II			
II		PUNIME NE KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	124		
2	3.158/5a	Transport dheu me auto 5km	m ³	124		
3	3 An. 8	Mbushje me çakell shkembor	m ³	62		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	310		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	6.00		
			SHUMA II			
III		PUNIME TROTUARE(1x1 m)				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	41.25		
2	3.158/5a	Transport dheu me auto 5km	m ³	41.25		
3	3 An. 8	Mbushje me çakell shkembor	m ³	16.5		
4	3.208	Shtrese çakelli T=10cm	m ²	310		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m ²	310		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	220		
7	2/262/4	Beton per fiksim bordure C16/20	m ³	6.6		
8	2.109/2	Shtrese betoni trotuari	m ³	31		
			SHUMA III			
6. PUNIME VEPRA ARTI (MURE MBAJTESE)						
1	3.105/a	Germim dheu me eskavator zinxhir 0.5 m ³ , ne kanale gjeresi deri 2 m, prani uji ~1m, kategoria IV, me shk ne mjet	m ³	62		
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	62		
3	3.243	Struktura monolite betoni C 16/20 per muret rrethuese	m ³	98		

	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	0.78		
	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	3.4		
		SHUMA 6	ton			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per elektrikun ndricimin	ml	180		
2	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	5		
3	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1		
		SHUMA IV				
		SHUMA H				

OBJEKTI : Ndertim Rruga "Haziz Ndreu " Paskuqan 2 Koder , Bashkia Kamez

B=6 m , basfalt=4.5 kunet=0.5m , trotuar 1x1 m

L= 240

I	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I		PUNIME NE RRUGE				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	216		
2	3.158/5a	Transport dheu me auto 5km	m ³	216		
3	An. 8	Mbushje me çakell shkembor	m ³	108		
4	3.211	Shtrese çakelli T=20cm	m ²	1080		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	1080		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	1080		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	1080		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	90.00		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	2.25		
10	An.	Ngritje pusete+kapak gize	cope	7		
11	An.	Spostim shtyllash	cope	6.00		
12	2/426/2	Prishje mure me blloqe + transport	m ³	144		
13	An.152	Vizime me boje bikomponente 15cm	ml	720		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
		SHUMA I				
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	96		
2	3.158/5a	Transport dheu me auto 5km	m ³	96		
3	3 An. 8	Mbushje me çakell shkembor	m ³	48		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	240		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	12		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	6.86		
		SHUMA II				
II		PUNIME NE KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	96		
2	3.158/5a	Transport çakelli me auto 5km	m ³	96		
3	3 An. 8	Mbushje me çakell shkembor	m ³	48		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	240		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	6.00		
		SHUMA II				
III		PUNIME TROTUARE(1x1 m)				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	94.40		
2	3.158/5a	Transport dheu me auto 5km	m ³	94.40		
3	3 An. 8	Mbushje me çakell shkembor	m ³	47.20		
4	3.208	Shtrese çakelli T=10cm	m ²	200.6		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m ²	200.6		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	480		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	14.4		
8	2.109/2	Shtrese betoni trotuari	m ³	20.06		
		SHUMA III				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	236		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndricimin	ml	236		
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	7		

4	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1		
			SHUMA IV			
			SHUMA I			

OBJEKTI : Ndertim Rruga "Erfan Strazimiri " Paskuqan 2 , Bashkia Kamez

B=6 m , basfalt=4.5 kunet=0.5m , trotuar 1x1 m

L= 155

J	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	139.50		
2	3.158/5a	Transport dheu me auto 5km	m ³	139.50		
3	An. 8	Mbushje me çakell shkembor	m ³	69.75		
4	3.211	Shtrese çakelli T=20cm	m ²	697.50		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	697.50		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	697.50		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	697.50		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	58.13		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.45		
10	An.	Ngritje pusete+kapak gize	cope	4		
11	An.	Spostim shtyllash	cope	3.88		
12	2/426/2	Prishje mure me blloqe + transport	m ³	93		
13	An.152	Vizime me boje bikomponente 15cm	ml	465		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		

SHUMA I

II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	62		
2	3.158/5a	Transport dheu me auto 5km	m ³	62		
3	3 An. 8	Mbushje me çakell shkembor	m ³	31		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	155		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	7.75		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	4.43		

SHUMA II

III PUNIME TROTUARE(1x1 m)						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	30.0		
2	3.158/5a	Transport dheu me auto 5km	m ³	30.0		
3	3 An. 8	Mbushje me çakell shkembor	m ³	30.0		
4	3.208	Shtrese çakelli T=10cm	m ²	152.0		
5	3.212/b	Shtrese stabilizanti ne trotuar T=10cm	m ²	152.0		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	310		
7	2/262/4	Beton per fiksim bordure C16/20	m ³	9.3		
8	2.109/2	Shtrese betoni trotuari	m ³	15		

SHUMA III

II PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	40.18		
2	3.158/5a	Transport dheu me auto 5km	m ³	40.18		
3	3 An. 8	Mbushje me çakell shkembor	m ³	56		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	155		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	4.00		

SHUMA II

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per elektrikun	ml	250		
2	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	7		
3	An-19	F.v puseta betoni me kapak gize 80x80x100mm	cope	1		

SHUMA IV

SHUMA J

OBJEKTI : Ndertim Rruga "Vehbi Dibra " Paskuqan 2 , Bashkia Kamez

B=6.2 m , basfalt=4.5 kunet=0.5m , trotuar 1x1 m

L= 176

K	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						

NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	158.4		
2	3.158/5a	Transport dheu me auto 5km	m ³	158.4		
3	An. 8	Mbushje me çakell shkembor	m ³	79.2		
4	3.211	Shtrese çakelli T=20cm	m ²	792		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	792		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	792		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	792		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	136.50		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	3.41		
10	An.	Ngritje pusete+kapak gize	cope	6		
11	An.	Spostim shtyllash	cope	4.40		
12	2/426/2	Prishje mure me blloqe + transport	m ³	105.6		
13	An.152	Vizime me boje bikomponente 15cm	ml	528		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
			SHUMA I			
II		PUNIME NE KUB				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	82		
2	3.158/5a	Transport dheu me auto 5km	m ³	82		
3	3 An. 8	Mbushje me çakell shkembor	m ³	41		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	205		
	3.an/2t	F.V. Tuba I brinjezuar Ø 400	ml	205		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	8.8		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	5.03		
			SHUMA II			
II		PUNIME NE KUN				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	45.6192		
2	3.158/5a	Transport çakelli me auto 5km	m ³	45.6192		
3	3 An. 8	Mbushje me çakell shkembor	m ³	63		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	176		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	6.00		
			SHUMA II			
III		PUNIME TROTUARE(1x1 m)				
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	54.0		
2	3.158/5a	Transport dheu me auto 5km	m ³	54.0		
3	3 An. 8	Mbushje me çakell shkembor	m ³	54.0		
4	3.208	Shtrese çakelli T=10cm	m ²	149.6		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m ²	149.6		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	352		
7	2/262/4	Beton per fiksime bordure C16/20	m ³	10.56		
8	2.109/2	Shtrese betoni trotuari	m ³	27.5		
			SHUMA III			
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.654/1	F.V. Tub korrogato Ø80 per telefonine	ml	250		
2	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	250		
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	7		
			SHUMA IV			
			SHUMA G			

OBJEKTI : Ndertim Rruga "Nikoll Kaçorri + DEDE PLANI " Paskuqan 2 , Bashkia Kamez

B=5.2m , basf= 4.0 m + kunete 2x0.5 m

L= 220

L	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I						
PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	210		
2	3.158/5a	Transport dheu me auto 5km	m ³	210		
3	An. 8	Mbushje me çakell shkembor	m ³	105		
4	3.211	Shtrese çakelli T=20cm	m ²	880		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	880		

6	3.222/2	Shtrese binderi 1x6 cm	m ²	880	
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	880	
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	82.50	
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	2.06	
10	An.	Ngritje pusete+kapak gize	cope	7	
11	An.	Spostim shtyllash	cope	5.50	
12	2/426/2	Prishje mure me blloqe + transport	m ³	132	
13	An.152	Vizime me boje bikomponente 15cm	ml	660	
14	An.96	Tabele sinjalistike 60-90cm	cope	4	

SHUMA I

II PUNIME NE KUB					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	88	
2	3.158/5a	Transport dheu me auto 5km	m ³	88	
3	3 An. 8	Mbushje me çakell shkembor	m ³	44	
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	220	
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	11	
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	6.29	

SHUMA II

II PUNIME NE KUN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	60	
2	3.158/5a	Transport dheu me auto 5km	m ³	60	
3	3 An. 8	Mbushje me çakell shkembor	m ³	79	
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	220	
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	4.00	

SHUMA II

III PUNIME TROTUARE					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	440	
2	2/262/4	Beton per fiksime bordure C16/20	m ³	13.2	

SHUMA III

SHUMA L

OBJEKTI : Ndertim Rruga "Demir Gashi " Paskuqan 2 , Bashkia Kamez

B= 5.3 m , basfalt=4 kunet=2x0.5m ,

L= 124

M	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	120.0		
2	3.158/5a	Transport dheu me auto 5km	m ³	120.0		
3	An. 8	Mbushje me çakell shkembor	m ³	59.0		
4	3.211	Shtrese çakelli T=20cm	m ²	496.0		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	496.0		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	496.0		
7	3.226/1	Shtrese asfaltbetoni 1x4cm	m ²	496.0		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	51.02		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.3		
10	An.	Ngritje pusete+kapak gize	cope	7.0		
11	An.	Spostim shtyllash	cope	3.0		
12	2/426/2	Prishje mure me blloqe + transport	m ³	74.4		
13	An.152	Vizime me boje bikomponente 15cm	ml	248.0		
14	An.96	Tabele sinjalistike 60-90cm	cope	4.0		
SHUMA I						
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	49.6		
2	3.158/5a	Transport dheu me auto 5km	m ³	49.6		
3	3 An. 8	Mbushje me çakell shkembor	m ³	24.8		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	124		
	3.an/2t	F.V. Tuba I brinjezuar Ø 400	ml	110		
5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	6.2		

6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	3.54	
			SHUMA II		
II PUNIME NE KUN					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.139	Germim dheu me eskavator	m ³	40	
2	3.158/5a	Transport dheu me auto 5km	m ³	40	
3	3 An. 8	Mbushje me çakell shkembor	m ³	45	
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	124	
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	3.00	
			SHUMA II		
III PUNIME TROTUARE(1x1 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	248.0	
2	2/262/4	Beton per fiksime bordure C16/20	m ³	7.44	
3	2.109/2	Shtrese betoni trotuari	m ³	8.50	
			SHUMA III		
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA	
1	3.654/1	F.V. Tub korrogato Ø80 per elektrikun + ndricimin rrugore	ml	125	
3	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	4	
			SHUMA IV		
			SHUMA M		

OBJEKTI : Nderim Rruga "Iljaz Pash Dibra " Paskuqan 2 , Bashkia Kamez

B=6 m , basfalt=4 kunet=2x0.5m , trotuar 1x1 m

L= 194

M	An.	Emertimi i Punimeve	Njesia	Sasia	Cmimi	Vlera
I PUNIME NE RRUGE						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	194		
2	3.158/5a	Transport dheu me auto 5km	m ³	194		
3	An. 8	Mbushje me çakell shkembor	m ³	132		
4	3.211	Shtrese çakelli T=20cm	m ²	776		
5	3.212/b	Shtrese stabilizanti t=10cm	m ²	776		
6	3.222/2	Shtrese binderi 1x6 cm	m ²	776		
7	3.226/1	Shtrese asfaltobetoni 1x4cm	m ²	776		
8	2/111/2	Mure betoni C12/15(themel,xokol betoni)	m ³	46.0		
9	3.288	F.V Hekur betoni I zakonshem O > 10 mm	ton	1.15		
10	An.	Ngjitje pusete+kapak gize	cope	3		
11	An.	Spostim shtyllash	cope	4.00		
12	2/426/2	Prishje mure me blloqe + transport	m ³	86		
13	An.152	Vizime me boje bikomponente 15cm	ml	582		
14	An.96	Tabele sinjalistike 60-90cm	cope	4		
			SHUMA I			
II PUNIME NE KUN						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	72		
2	3.158/5a	Transport dheu me auto 5km	m ³	72		
3	3 An. 8	Mbushje me çakell shkembor	m ³	36		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	180		
5	An - 20	Pusete shkarkimi b/a, 80 x 80 cm, h = 150 cm	cope	6.00		
			SHUMA II			
II PUNIME NE KUB						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	77.6		
2	3.158/5a	Transport dheu me auto 5km	m ³	77.6		
3	3 An. 8	Mbushje me çakell shkembor	m ³	38.8		
4	3.an/1t	F.V. Tuba I brinjezuar Ø 315	ml	194		

5	2.262/4	Shtrese betoni c 16/20Kunete betoni M - 200	m ³	19.4		
6	2.An.23	Puseta shiu me zgare 40x60 + kapak gize	cope	6.00		
SHUMA II						
III	PUNIME TROTUARE(1x1 m)					
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
1	3.139	Germim dheu me eskavator	m ³	112.00		
2	3.158/5a	Transport dheu me auto 5km	m ³	112.00		
3	3 An. 8	Mbushje me çakell shkembor	m ³	47.20		
4	3.208	Shtrese çakelli T=10cm	m ²	236.0		
5	3.212/a	Shtrese stabilizanti ne trotuar T=5cm	m ²	236.0		
6	3.617	F.V. Bordura betoni e parapregatitur M-250 15x25 cm	ml	388		
7	2/262/4	Beton per fiksim bordure C16/20	m ³	11.64		
8	2.109/2	Shtrese betoni trotuari	m ³	23.6		
SHUMA III						
Punime Elektrike						
NR.	Nr.An	PERSHKRIMI I PUNIMEVE	NJESIA	SASIA		
194	3.654/1	F.V. Tub korrogato Ø80 per elektrikun, ndriçimin	ml	194		
2	3An/55	F.v puseta elektrike kontrolli PVC 40x40 x40	cope	6		
SHUMA IV						
SHUMA G						
Shuma e Rrugeve totale						
TVSH 20%						
TVSH TOTALE						

V.O. Çmimet jane vendosur ne baze te vkm nr 629 date 15.07.2015

Preventivues:

Ing. Hajredin MURGU



Drejtori i Pergjithshem
Elvis Gjika



Drejtori P.I-se
Ing. Flora MUÇA



MIRATOI
Rakip SULI

KRYETAR

