

BASHKIA GRAMSH

PREVENTIV

OBJEKTI "SISTEMIM ASFALTIM I LAGJES XHILE LIÇI" BASHKIA GRAMSH

INVESTITORI : BASHKIA GRAMSH

Nr	Nr.An	Emertimi	Njesia	Sasia	Çmimi	Vlera
	I	PUNIME PRISHJE				
1	2.426/5	Prishje mure betoni	m ³	2		0
2	AN	Prishje mure guri e puseta kontrolli	m ³	15		0
3	2.426/1	Prishje mur tulle (rrethim)	m ³	24		0
4	3. An-48	Prishje mur guri (rrethim)	m ³	44		0
5	3.An-49	Prishje mure + struktura betoni	m ³	4.8		0
6	2.37/5a	Ngarkim transport Auto mbeturina - 5 km	m ³	250		0
		SHUMA I				0
1	II	PUNIME NE RRUGE E SHESHE TROTUARE				
2	3.An	Skarifikim shtrese asfalti me makineri	m ²	350		0
3	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ ,shkark,n	m ³	160		0
4	3.138	Germim dheu me ekskavator goma 0.25 m ³ ,themel	m ³	92		0
5	3.325	Mur guri mbajtes e themele me gur mozaik	m ³	72		0
6	3.322	Mur guri mbajtes themeli ll/b M - 25	m ³	23		0
7	3.242	Brez betoni C 12/15	m ³	6		0
8	3.193/b	Shtrese zhavor lumi t=15 cm ne sheshe cilindrim	m ²	520		0
9	3.210	Shtrese cakullit = 15 cm perhapur me makineri	m ²	810		0
10	3.212/b	Shtrese stabilizanti 10 cm	m ²	810		0
11	An	Sperkatje me emulsion bituminoz 0.5 l/m ²	m ²	810		0
12	3.222/2	Shtrese binderi 6 cm	m ²	810		0
13	3.226/1	Shtrese asfatlbetoni 4 cm	m ²	810		0
14	3.616	F.V bordura betoni p.p. 15 x 25 cm	ml	570		0
15	3.617/2	F.V bordura betoni p.p. 15 x 35 cm	ml	30		0
16	3.243/1	Struktura te holla betoni C16/20 (shkalle)	m ²	2		0
17	3.243	Shtrese betoni C 16/20 t = 15 cm	m ³	70		0
18	3.620	Trotuar me 6 cm me pllaka betoni	m ²	60		0
		SHUMA II				0
	III	PUNIME KANALIZIMI UJRA SHIU				
1	3.87/a	Germim dheu kanal eskavator goma 0.25 m ³ (50ml)	m ³	50		0
2	AN - 22	Ndertim puseta ujembledhese k. gize 40x40	cope	3		0
3	3.An/2t	Tuba te brinjezuar HDPE ø 400	ml	45		0
4	3.182/a	Shtrese rere nen e mbi tub 2x10 cm (50 ml)	ml	50		0
5	2.575	Pusete kontrolli 1 x1 x 1.5 m	cope	1		0
6	An.575	Mbingritje puseta kontrolli k. gize ø 100	cope	4		0

7	2.190	Mbushje ngjeshje dheu mbulim kanali	m ³	20		0
8	3.243	Betonim kunete betoni M -16/20 (200mx0.4x0.08)	m ³	6.4		0
		SHUMA				0
	IV	PUNIME RRETHIMI				
1	3.138	Germim dheu per themel	m ³	19.5		0
2	3.322	Mur guri themel xokol ll/ç M - 25	m ³	30		0
3	3.242	Brez betoni C 12/15 mbi mur	m ³	3.6		0
4	2.414	F.V kangjella metalike me profile	ton	1.4		0
		SHUMA				0
	V	PUNIME NDRICIMI				
1	3.89/b	Germim dheu per kanal	m ³	49		0
2	3.654/1	F.V. tub i brinjezuar ø 80	ml	132		0
3	2.575	Shtrese rere nen e mbi tub 2x10 cm	m ²	90		0
4	.142/2.2	F.V .kabell ndricimi	ml	183		0
5	An.57/b	F.V .puseta PVC 40x40x40	cope	6		0
6	3.An/53	F.V. shtylla metalike konike h=7 m	cope	6		0
7	3.An/57	F.V. krahe shtylle metalike	cope	6		0
8	3.An/et	F.V. elektroda tokezimi zink+cu 1.5 m	cope	6		0
9	2.9-98	F.V shirit zinku +cu 30 x3 mm tokezim	ml	12		0
10	3.An	F.V. ndricuesa smart VP CL1 CR M-S 250W	cope	6		0
		SHUMA				0
	VI	PUNIME GJELBERIMI				
1	An	Mbushje me dhera te pasuruar	m ²	150		0
2	An	Sistemim nivelim siperfaqe e punime	m ²	151		0
3	3.643	Mbjellje bari dekorativ	m ²	150		0
4	An 164	F.V. fidane peme dekorativ	cope	6		0
5	An 165	F.V. fidne shkurre dekorative	leke	12		0
6	An	F.V. minikosha mbeturinash	cope	4		0
7	An	F.V.stola metalike	cope	4		0
		SHUMA				0
		SHUMA I - VI				0
		TVSH 20%				0
		SHUMA TOTAL				0

PUNOI
ING. Eva ISMAILAJ

MIRATOHET
KRYETARI I BASHKISE
BESION AJAZI