

PREVENTIV PUNIMESH NDERTIMORE

NR.	KODI	EMËRTIMI I PUNIMEVE.	NJËSIA	SASIA
		1. PUNIME SHPYLLEZIMI		
1	3.2	Prerje bime te vogla ø ~ 10cm	m2	1240
2	3.3	Preje e sistemim pemesh ø 10 ~ 20 cm	copë	55
		SHUMA 1:		
		2. PUNIME GERMIMI		
3	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet	m3	850
4	3.158/5a	Transport dheu me auto deri 5.0 km	m3	7377
		SHUMA 2:		
		3. PUNIME DHEU		
5	2.28	Germim dheu themele e plinta me b>2m, ekskavator me zinxhir 0.25m3,shkarkimi ne auto	m3	5310
7	2.47/a n	Germim shkemb mesatar me çekiç me ekskavator me zinxhir	m3	1298
8	2.37/5 b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	235
9	2.26	Germim dheu themele e plinta me b>2m, ekskavator me goma 0.25m3,shkarkimi ne auto	m3	235
10	2.37/5 b	Transport materiale ndertimi, dheu me auto deri 10.0 km	m3	265
11	2.26	Germim dheu themele e plinta me b>2m, ekskavator me goma 0.25m3,shkarkimi ne auto	m3	265
		SHUMA 3:		
		4. PRISHJE		
12	2.426/3	Prishje shtresa betoni	m3	12
		SHUMA 4:		
		6. PUNIME SHITRESASH		
14	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	55
15	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m3	235
16	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri	m2	1875
		SHUMA 6:		
		7. NDERTIMI I VEPRAVE TE ARTIT+KANALIZIME		
17	3.405	Prishje struktura prej guri	m3	55
		SHUMA 7:		
		8. PUNIME BETONI DHE B/A		
18	2.574	Trare e arkitrare b/a C 25/30	m3	13
19	2.117/1b	Kollona b/a monolite C 25/30 h ~ 4m	m3	18
20	2.130/1a	Mure b/a t = 21-30cm, h ~ 4m C 20/25	m3	13
21	2.585	Plinta b/a C25/30	m3	22
22	2.122/1a	Soleta te plota b/a C 20/25 t = 10 cm, h ~ 4m	m3	22
23	2.125/1a	Soleta b/a me polisterol dhe rrjete teli C 20/25 t=30cm, h~6m	m2	115
24	2.121	Breza b/a monolit C 16/20	m3	1.2
25	2.574	Trare e arkitrare b/a C 25/30	m3	1.3
26	2.117/1b	Kollona b/a monolite C 25/30 h ~ 4m	m3	4
27	2.130/1a	Mure b/a t = 21-30cm, h ~ 4m C 20/25	m3	22
28	2.122/1b	Soleta te plota b/a C 25/30, h~4 m	m3	72
29	2.122/1b	Soleta te plota b/a C 25/30, h~4 m	m3	3
30	2.262/4b	Pllake themeli, trare e bazamente b/a C 25/30	m3	13
31	2.122/1b	Soleta te plota b/a C 25/30, h~4 m	m3	8
32	2.201	Themel betoni C16/20	m3	67
33	2.130/1a	Mure b/a t = 21-30cm, h ~ 4m C 20/25	m3	52.5
		SHUMA 8:		
		9. PUNIME SHITRESASH 2		
34	2.262/3	Shtrese betoni C 12/15	m3	15

35	2.262/ 3	Shtrese betoni C 12/15	m3	40
36	2.262/ 3	Shtrese betoni C 12/15	m3	5
37	2.267/ 1	Shtrese me pllaka porcelanat	m2	190
38	2.277	Shtrese lluster çimento 1:2, t=30mm	m2	310
39	2.273/ 5	Shtrese me pllaka mermeri t=3cm	m2	30
		SHUMA 9:		
		10. PUNIME HEKUR BETONI		
40	2.166/ 1a	F.V. Hekur betoni periodik Ø > 12 mm	ton	36
41	2.166	F.V. Hekur betoni periodik Ø 6 - 10 mm	ton	26
42	2.182	F.V. Konstrukione metalike te thjeshta.	ton	32
		SHUMA 10:		
		11. PUNIME HIDROIZOLIMI DHE ÇATITE		
43	2.256/ b	Mbulim çatie me panele sanduich	m2	302
44	2.197	Hidroizolim me emulsion bitumi dhe 2 k katrama	m2	140
45	2.239/ a	Shtrese termoizoluese me polisterol t=10 cm	m2	120
46	2.203	Veshje korrnize llamarine xingat	m2	22
47	2.209	Ulluk shkarkimi vertikal me llamarine xingat Ø 100	ml	33
48	2.212	Ulluk shkarkimi horizontal me llamarine xingat 33cm	ml	30
49	2.196/ b	Hidroizolim me nje shtres astar me baze cimento. Pergatitur nga dy komponente A+B	m2	185
		SHUMA 11:		
		12. PUNIME MURATURE TULLE		
50	2.71/1	Mur me tulla te lehtesuara dopio deri 8 m, LL.P. M-15	m3	35
51	2.86.	Mur me tulla me 6 vrima, t=12cm h~3m, ll perz M 15	m3	4
		SHUMA 12:		
		13. PUNIME TAVANI DHE SUVATIMI		
52	2.324a	Plintuse pllake grez	ml	175
53	2.297/ b	Tavan i varur me pllaka gipsi 60x60cm	m2	5
54	2.297/ a	Veshje tavani me kartonxhes	m2	198
55	2.330/ 1	Patinim tavani me stuko	m2	198
56	2.331	Suva e zakonshme fasade mur tulle ~ 8m	m2	160
57	2.358/ b	Veshje fasade me polisterol t=5cm + rrjete + suva.	m2	160
58	2.326	Veshje me pllake majolike	m2	85
59	2.310	Suva brenda mur tulle ~ 4m, me krah, llaç perzier M 25	m2	140
60	2.328/ 1	Patinim muri me stuko	m2	430
		SHUMA 13:		
		14. PUNIME DYER DRITARE		
61	2.383/ 1	F.V. Dyer te brendeshme druri cilesi e I-re.	m2	21.3
62	2.395/ a	Dyer d/alumini me mbushje element d/a.	m2	6.7
		SHUMA 14:		
		15. PUNIME BOJATISJE		
63	2.404/ 1	Boje hidroplastike cilesi e larte	m2	760
		SHUMA 15:		
		16. PUNIME TE NDRYSHME		
64	3.620	Trotuar, me 6 cm beton, me pllaka	m2	20
65	3.616/ a	F.V. Bordura betoni 15x25cm	m	15
		SHUMA 16:		
		17. D. SINJALET DHE PAJISJET SHTESE. NGADALESUESIT E SHPEJTESISE		
66	3.961	F.V. Fidane Peme dekorative	copë	10
		SHUMA 17:		
		18. ANALIZA JASHTJE LISTE		
67	AnAn. 1	Panel sanduic me termoizolim, ngjyre jeshile per fasade, t=10cm kundra lageshtires	m2	470
68	AnAn. 2	Ndertim muri gipsi dopio pllake me strukture metalike e i pajisur me lesh guri t=5cm per termoizolim	m2	270
69	AnAn. 3	F.V dritare duralumini dopio xhame me kase te zeze, me gaz argon	m2	62

70	AnAn. 4	Shtrim me beton me stampa t=15cm, me zgare hekuri Ø 8mm	m2	1875
71		Qepena me panel sanduic te pajisjura me elektromotor	m2	100

72		F.V Kangjella metalike	m2	210
		SHUMA 18:		
Shuma Analiza				
Fondi Rezervë (5.0%)				
Shuma Analiza + Fondi Rezervë (5.0%)				
Shuma TVSH (20%)				
Shuma me TVSH				
Totali				